



US Army Corps
of Engineers

REPAIR, EVALUATION, MAINTENANCE, AND
REHABILITATION RESEARCH PROGRAM

TECHNICAL REPORT REMR-OM-1

EVALUATION OF EXISTING CONDITION
RATING PROCEDURES FOR CIVIL WORKS
STRUCTURES AND FACILITIES


by

Enno Koehn, Anthony M. Kao

Construction Engineering Research Laboratory

DEPARTMENT OF THE ARMY
US Army Corps of Engineers
PO Box 4005, Champaign, Illinois 61820-1305

DTIC
ELECTE
JUL 31 1986
S D B



May 1986
Final Report

Approved For Public Release; Distribution Unlimited

DTIC FILE COPY

Prepared for DEPARTMENT OF THE ARMY
US Army Corps of Engineers
Washington, DC 20314-1000
Under Civil Works Research Work Unit 32280

86 7 31 045

The following two letters used as part of the number designating technical reports of research published under the Repair, Evaluation, Maintenance, and Rehabilitation (REMR) Research Program identify the problem area under which the report was prepared:

<u>Problem Area</u>		<u>Problem Area</u>	
CS	Concrete and Steel Structures	EM	Electrical and Mechanical
GT	Geotechnical	EI	Environmental Impacts
HY	Hydraulics	OM	Operations Management
CO	Coastal		

For example, Technical Report REMR-OM-1 is the first report published under the Operations Management problem area.

Destroy this report when no longer needed. Do not return
it to the originator.

The findings in this report are not to be construed as an official
Department of the Army position unless so designated
by other authorized documents.

The contents of this report are not to be used for
advertising, publication, or promotional purposes.
Citation of trade names does not constitute an
official endorsement or approval of the use of
such commercial products.

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Technical Report REMR-OM-1	2. GOVT ACCESSION NO. AD-A170391	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) EVALUATION OF EXISTING CONDITION RATING PROCEDURES FOR CIVIL WORKS STRUCTURES AND FACILITIES		5. TYPE OF REPORT & PERIOD COVERED Final report
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Enno Koehn Anthony Kao John Carr		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Construction Engr Research Laboratory P.O. Box 4005 Champaign, IL 61820-1305		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Civil Works Research Work Unit 32280
11. CONTROLLING OFFICE NAME AND ADDRESS DEPARTMENT OF THE ARMY U.S. Army Corps of Engineers Washington, D.C. 20314-1000		12. REPORT DATE May 1986
		13. NUMBER OF PAGES 150
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES A report of the Operations Management problem area of the Repair, Evaluation, Maintenance, and Rehabilitation (REMR) Research Program. This report is available from the National Technical Information Service, 5285 Port Royal Road, Springfield, Virginia 22161.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) maintenance management irrigation systems civil works structures flood control highways bridges		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This investigation has compiled information on numerous maintenance procedures used on civil works structures for the purpose of finding an overall procedure applicable to civil works projects. The information was obtained from available literature and from national and state agencies responsible for civil works maintenance programming. (Cont'd)		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

BLOCK 20. (Cont'd)

For each data source, a detailed inspection was made of the procedural components involved in maintenance procedures, such as checklists, manuals, rating systems, computer applications, technical and professional requirements, frequency of inspection, and repeatability. The various systems were then evaluated and compared. No appropriate rating system was found that applied directly to the periodic maintenance of civil works structures, and no system appeared to be easily usable and reliable when used by inexperienced raters. However, the Corps of Engineers Pavement Maintenance Management System (PAVER) and the Federal Highway Bridge Inspection Program appear to offer approaches that, with modifications, could be applied to Civil Works maintenance.

UNCLASSIFIED


SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

PREFACE

The study reported here was authorized by Headquarters, U.S. Army Corps of Engineers (HQUSACE), as part of the Operations Management problem area of the Repair, Evaluation, Maintenance, and Rehabilitation (REMR) Research Program. The work was performed under Work Unit 32280, "Development of Uniform Evaluation Procedures and Condition Index for Deteriorated Structures and Equipment," for which Dr. Anthony M. Kao is Principal Investigator. Mr. John R. Mikel (DAEN-CWO) is the REMR Technical Monitor for this work.

Mr. Jesse A. Pfeiffer, Jr., DAEN-RDC, is the REMR Coordinator at the Directorate of Research and Development, HQUSACE; Messrs. Mikel and Bruce L. McCartney (DAEN-CWH-D) and Dr. Tony C. Liu (DAEN-ECE-D) serve as the REMR Overview Committee; Mr. William F. McCleese (WESSC-A), U.S. Army Engineer Waterways Experiment Station, is the REMR Program Manager; Dr. Kao is also Problem Area Leader for the Operation Management problem area.

This work was conducted by the U.S. Army Construction Engineering Research Laboratory (USA-CERL) during the period October 1984 to December 1985 under the general supervision of Dr. R. Quattrone, Chief of the Engineering and Materials Division. COL Paul J. Theuer is Commander and Director of USA-CERL, and Dr. L. R. Shaffer is Technical Director.



Accession For	
RESEARCH	<input checked="" type="checkbox"/>
TECHNICAL	<input type="checkbox"/>
ADMINISTRATIVE	<input type="checkbox"/>
GENERAL	<input type="checkbox"/>
OTHER	<input type="checkbox"/>
A 10 1000000000	
Dist 1000000000	
A-1	23

CONTENTS

	<u>Page</u>
PREFACE.	1
PART I: INTRODUCTION.	5
Background.	5
Objective	6
Approach.	6
Mode of Technology Transfer	7
PART II: CONCRETE/MASONRY DAMS AND CANALS	8
Maintenance Inspection Procedures	8
U.S. Army Corps of Engineers.	8
Bureau of Reclamation	9
Los Angeles Flood Control District.	10
Tennessee Valley Authority.	11
Ohio Department of Natural Resources.	11
North Carolina Department of Environmental Resources.	11
Pennsylvania Department of Environmental Resources.	11
Colorado Division of Water Resources.	12
Kansas Division of Water Resources.	12
Pacific Gas & Electric Company.	12
Federal Emergency Management Agency (FEMA).	13
Evaluation.	14
Part III: ROCK AND EARTH DAMS	15
Maintenance Inspection Procedures	15
U.S. Army Corps of Engineers.	15
Bureau of Reclamation	16
Resources Agency of California.	16
Ohio Department of Natural Resources.	16
Virginia Bureau of Water Control Management	17
North Carolina Department of Natural Resources.	18
Pennsylvania Department of Environmental Resources.	18
Colorado Division of Water Resources.	19
Kansas Division of Water Resources.	20
Other agencies and publications	20
Evaluation.	21
PART IV: SPILLWAYS, STILLING BASINS AND OUTLET WORKS.	22
Maintenance Inspection Procedures	22
Nashville District.	22
Portland/Walla Walla District	23
Omaha District.	23
Rock Island District.	23
Headquarters, U.S. Army Corps of Engineers (HQUSACE).	24
Evaluation.	24

PART V: LOCKS, LOCKWALLS, LOCKGATES, OPERATING EQUIPMENT.	25
Maintenance Inspection Procedures	25
Nashville District.	25
Portland/Walla Walla Districts.	26
Rock Island District.	26
Evaluation.	27
PART VI: POWERHOUSES AND PUMPING PLANTS	28
Maintenance Inspection Procedures	28
U.S. Army Corps of Engineers.	28
Bureau of Reclamation	29
Los Angeles Flood Control District.	31
Kansas Division of Water Resources.	31
Federal Emergency Management Agency (FEMA).	32
Evaluation.	32
PART VII: BRIDGES AND ROADS	33
Maintenance Inspection Procedures	33
Federal Highway Bridge Replacement and Rehabilitation Program	33
Corps of Engineers' Pavement Maintenance Management for Roads and Parking Lots (PAVER).	33
Indiana Department of Highways.	34
Evaluation.	35
PART VIII: MISCELLANEOUS FACILITIES	36
Maintenance Inspection Procedures	36
TRADOC's BMAR and DMAR Rating Systems	36
FORSCOM Regulation 420-3.	37
U.S. Army Corps of Engineers, Southwestern Division	38
The Resources Agency of the State of California	38
Evaluation.	39
PART IX: CONCLUSIONS.	40
REFERENCES	41
TABLES 1-7	
APPENDIX A: CHECKLISTS AND EXPLANATORY MATERIALS FOR CONCRETE/ MASONRY DAMS.	A1
APPENDIX B: CHECKLISTS AND EXPLANATORY MATERIALS FOR ROCK AND EARTH DAMS.	B1
APPENDIX C: CHECKLISTS AND EXPLANATORY MATERIALS FOR SPILLWAYS, STILLING BASINS, AND OUTLET WORKS	C1
APPENDIX D: CHECKLISTS AND EXPLANATORY MATERIALS FOR LOCKS, LOCKWALLS, LOCKGATES, AND OPERATING EQUIPMENT.	D1

APPENDIX E: CHECKLISTS AND EXPLANATORY MATERIALS FOR POWERHOUSES AND PUMPING PLANTS.	E1
APPENDIX F: CHECKLISTS AND EXPLANATORY MATERIALS FOR BRIDGES AND ROADS	F1
APPENDIX G: CHECKLISTS AND EXPLANATORY MATERIALS FOR MISCELLANEOUS FACILITIES.	G1
DISTRIBUTION	

EVALUATION OF EXISTING CONDITION RATING PROCEDURES FOR
CIVIL WORKS STRUCTURES AND FACILITIES

PART I: INTRODUCTION

Background

1. Civil works structures, which include highways, bridges, navigation, hydropower, and flood control facilities, and irrigation and drainage systems, are subject to varying degrees of deterioration. Periodic care and maintenance are required to prevent or decrease the development of any unsatisfactory condition, such as abutment erosion, concrete cracks, and seepage through the embankment or structural foundation. To obtain the longest life and most efficient use of these facilities, a maintenance program is required that includes reliable checklists and procedures to systematically improve and replace deteriorated elements.

2. Many state and national agencies as well as international organizations and private firms set standards for civil works maintenance programs. Among the most active U.S. organizations are the U.S. Army Corps of Engineers, the Bureau of Reclamation, the Resources Agency of the California Department of Water Resources, the Tennessee Valley Authority, and the Los Angeles Flood Control District. The American Society of Civil Engineers and the National Academy of Sciences are the most active of the national organizations in publishing manuals and reports on maintenance activities. Many of these agencies use checklists, computer data systems, and other schemes to maintain civil works structures under their jurisdictions.

3. Use of effective maintenance management procedures on the Corps of Engineers' civil works structures could greatly reduce costs and lengthen facility life. Also, personnel whose duties include inspection and maintenance procedures may often be inexperienced at this type of work. Therefore, a study was needed that would demonstrate not only how effective the various systems are, but also how easy they are to use.

Objective

4. The objectives of this study were to (a) ascertain the state of the art of existing evaluation methods and condition indexes and to determine if any present system can be adapted for use on civil works structures and (b) determine the efficiency and reliability of these methods when used by inexperienced personnel.

Approach

5. Numerous government and private agencies were contacted and a literature search was conducted to determine existing civil works maintenance rating procedures used by organizations that maintain these types of facilities. For each group, procedural components (e.g., checklists, manuals, rating systems, computer applications, technical and professional requirements, frequency of inspection, and repeatability) were recorded and evaluated.

6. Parts II through VIII of this report evaluate maintenance procedures of the following civil works structures and facilities: concrete dams and canals; rock and earth dams; spillways, stilling basins, and outlet works; lock walls, lock gates, and operating equipment; powerhouses and pumping plants; bridges and roads; and miscellaneous facilities. Tables in each chapter rate maintenance procedures according to whether they include the following criteria:

- a. Checklists.
- b. Manual (explanatory) for maintenance inspection procedures.
- c. Rating system.
- d. Computer application.
- e. Technical evaluation with photographs.
- f. Requirement of professional engineer.
- g. Requirement of technical knowledge.
- h. Repeatability (a term used for maintenance systems and procedures that will yield identical results when performed by different individuals).
- i. Requirement of periodic inspection.

7. Agencies that use any or all of these criteria are indicated for each category of civil works structure. The appendices provide checklists, computer output, and other information applicable to each type of structure.

Mode of Technology Transfer

8. It is recommended that the results of this study be transferred through Engineer Technical Letters, Engineer Circulars, and the REMR Notebook (Ref. 29). No existing documents will be impacted by the results of this study.

PART II: CONCRETE/MASONRY DAMS AND CANALS

9. This chapter describes an investigation of maintenance programs conducted by agencies involved with operating concrete dams and canals. The agencies include two offices of the U.S. Army Corps of Engineers, the Bureau of Reclamation, the Los Angeles Flood Control District, the Tennessee Valley Authority, five state dam safety agencies, the Pacific Gas & Electric Company, and the Federal Emergency Management Agency. The following sections present detailed descriptions of the procedures used by these sources. Appendix A provides example checklists and information on concrete/masonry dams and canals.

Maintenance Inspection Procedures

U.S. Army Corps of Engineers

10. The Omaha District and Headquarters, U. S. Army Corps of Engineers (HQUSACE) have developed checklists to maintain and inspect concrete dams. However, neither program has a rating system that applies to the components of the maintenance tasks.

11. Omaha District. The Omaha District requires a technical inspection report consisting of photographs, interviews, notes, and data from monitoring devices. It requires that the observer construct an individual checklist for each site. This report, which is completed by an engineer, includes a descriptive section that assesses the general condition and offers an opinion about the urgency of repair. It also includes suggestions for possible remedial measures. A general guideline lists questions to be answered (Ref. 6) (see Figure A1).

12. HQUSACE. HQUSACE lists components that must be checked and conditions that should be monitored. Figure A2 lists the engineering data that must be included in any investigative report (Ref. 28). The HQUSACE guidelines present instructions for inspecting concrete dams that may serve as the basis for developing detailed checklists. This information is very useful for dam safety inspections but cannot be directly used for other facilities.

Bureau of Reclamation

13. The Bureau of Reclamation supervises the operation and maintenance of a large number of concrete dams in the western United States. It also has programs for detecting and redressing deficiencies at these facilities. The programs provide for periodic on-site examination of the structures and the completion of comprehensive checklists.

14. The checklists generally do not have a rating criterion or computer approach to data collection. They are used as guides, but can become a permanent part of the reference material kept for a specific site. They can also be modified to consider each dam's individual features.

15. All of the Bureau's checklists generally consist of a short outline of information and special instructions for conducting the examination. For the most efficient examination, it is necessary to include sheets with a list of items requiring additional work and for recording special problems. Use of photographs is also common for identifying special features. The following sections discuss checklists and rating procedures for two of the Bureau's programs.

16. RO&M Program. The Review of Operation and Maintenance (RO&M) Program is a Bureau-wide activity that schedules examinations of all project facilities, including concrete dams. It considers facilities in three classes: major structures, special features, and minor facilities. Storage dams and more complicated diversion dams are among the major structures, while less complicated dams are considered minor facilities.

17. Examinations under the RO&M Program are conducted by project and regional personnel on a biannual or triannual basis. For efficiency, three categories of recommendations are made according to the importance of the problem:

- a. Category 1: These recommendations relate to severe deficiencies, such as major cracks, in the concrete.
- b. Category 2: Recommendations under this category cover a wide range of important matters in which action is required to prevent or reduce further damage.
- c. Category 3: These recommendations are useful for the maintenance and consideration of less important items.

18. Figure A3 illustrates a checklist used by the RO&M Program for the maintenance of concrete dams (Refs. 8, 32). Space is provided for each item on the checklist for the comments of the rater/engineer.

19. SEED Program. The Safety Evaluation of Existing Dams (SEED) Program uses on-site examination and analysis to maintain the safety of concrete dams. The program includes an explanatory manual covering the Bureau's policies, principles, and concepts, as well as typical on-site examinations, examination reports, and checklists. Figure A4 illustrates a typical checklist (Ref. 34).

Los Angeles Flood Control District

20. The Los Angeles Flood Control District operates and maintains several flood-control reservoirs with a combined capacity of more than 106,000 acre-feet. Since debris swept down from steep mountain areas can be deposited on Los Angeles streets, causing property damage and loss of life, the district also operates and maintains debris dams and basins. For flooding protection, about 150 miles of permanent improvements have also been constructed; these consist of reinforced concrete channels and levees of riprap or concrete.

21. Following the Verdugo channel failure in September 1983, the district began an emergency program to identify, evaluate, and repair structural deficiencies in the open channel system. Because of the emergency action, it was concluded that under normal circumstances the structural inspection should be conducted by Operation and Maintenance (O&M) field personnel within the framework of the existing maintenance management system.

22. The inspections generally begin in March each year with sufficient resources allocated to conclude by the first of May. The district has provided detailed facility monitoring and inspection procedure for dams, debris basins, regulating basins, pumping plants, covered channels and storm drains, debris disposal areas, and inlets to underground systems.

23. A rating system for channel invert and walls is also available based on the severity of their distress (Figure A5). For instance, the deterioration of a channel wall is low if the hole's cross-sectional area is less than 0.25 sq ft. The deterioration is considered medium if the hole's cross-sectional area is between 0.25 and 0.50 sq ft and high if the area is greater than 0.50 sq ft. The rating system also includes the extent and

condition of exposed steel, spalling and pitting, scour, slab cracking, ground water seepage, joint damage, faulting, slab bulging, and wall cracking. Figure A6 shows the application of these rating procedures using a checklist for a channel inspection.

Tennessee Valley Authority (TVA)

24. The TVA information includes a checklist used for concrete dam inspection (Ref. 40). The only rating categories on the list are "satisfactory" and "unsatisfactory." A space is provided for comments if a rating is unsatisfactory. Photographs are also taken as a record for comparison over a span of years. There is no detailed rating system used by the TVA, and the computer is not used for data collection.

25. Lengthy reports are written and recommendations made by civil, mechanical, and electrical engineers (Figure A7).

Ohio Department of Natural Resources

26. The Ohio Department of Natural Resources (ODNR) encourages owners to thoroughly inspect their facilities visually at least twice a year. The forms provided by the ODNR are helpful for these inspections (Ref. 20).

27. The dam inspection checklists have different parts, with one part dealing with concrete dams. The forms require observations by an inspector, and there is space for general comments, sketches, and field measurements. Figure A8 illustrates a concrete dam inspection checklist.

North Carolina Department of Environmental Resources

28. The Dam Safety Section of the North Carolina Department of Natural Resources has established a dam inspection checklist (Ref. 19), part of which can be used for concrete dams (see Figure B7 of Appendix B). Information must be provided for different parts of the facility, and a section is also included for comments. Examiners complete a followup inspection report. The checklist does not contain a rating system or manual.

Pennsylvania Department of Environmental Resources

29. The Pennsylvania Department of Environmental Resources publishes a checklist for an annual dam inspection (Ref. 1). The owner performs a

comprehensive visual examination and takes photographs to provide the Department of Environmental Resources with information about the facility's condition.

30. The concrete/masonry dam section of the inspection checklist (Figure A9) includes observations and recommendations/remarks on seepage, junction of structures, drains, foundations, cracking, spalling, and staff gage or recorder. The inventory provides a subjective evaluation of the dam and photographs. There is no rating system.

Colorado Division of Water Resources

31. The Colorado Division of Water Resources has developed the Dam Safety Manual, which is designed to provide specific guidance that will enable the owner to maintain a safe dam, avoid costly repairs, and prolong the facility life (Ref. 5).

32. The manual includes guides for visual inspection, seepage, upstream slope, crest, downstream slope, monitoring and instrumentation, maintenance, standard operating procedures, emergency plans, Colorado laws, and fundamentals of concrete dams. The chapter on concrete dams covers problems associated with this type of facility. These include structural cracks, foundation weaknesses, cracks at construction joints, shrinkage cracks, and deterioration from spalling.

33. The manual also contains specific information that applies to different types of dams. It includes many diagrams and photographs that should be easily understood by nontechnical personnel (see Figure B9 of Appendix B). This manual has a checklist, but does not have a rating system.

Kansas Division of Water Resources

34. The Water Structures Section of the Kansas State Division of Water Resources publishes a checklist for inspecting concrete/masonry dams (Ref. 16). The listing requires comments on engineering and construction data at the time it is considered during the inspection. There is no rating system.

Pacific Gas & Electric (PG&E) Company

35. PG&E regulations require a comprehensive inspection of all company dams once a year by an experienced engineering specialist. The engineer must

also be aware of the facility's past performance. To provide this information, the following four forms or reports are required for each inspection (Refs. 23, 24):

- a. The "Water Collection Inspection Checklist" (Figure A10) is a comprehensive checklist that indicates any repair work or further inspection required.
- b. The "Dam Inspection Report" consists of data and/or a description of the general condition of the dam's various functional parts. There is also space for listing any work required.
- c. A summary of work required is sent to the appropriate PG&E department.
- d. A report is submitted to the appropriate department after completion of the repair work.

36. If inspection shows any signs of overall instability, the proper authorities are informed immediately. Items in this category are noted by an asterisk in the "Water Collection Inspection Checklist."

37. Routine inspections are made more frequently by operating personnel assigned to the dams. It is recommended that the operator use the "Water Collection Inspection Checklist"; however, he/she need not complete the form. The Divisions must maintain a list of inadequacies and corresponding corrective actions. The appropriate department is notified of any critical problems.

38. Special inspections are performed immediately after occurrences such as a moderate earthquake in the area, flooding, and other possible causes of problems.

Federal Emergency Management Agency (FEMA)

39. The material provided by FEMA does not contain any form of checklist or rating system. However, the information found in Federal Guidelines for Dam Safety is pertinent to dam inspection (Ref. 9). It states that checklists should be prepared to cover the various structural, electrical, and mechanical features involved. It also recommends inspection every 5 years by a licensed professional engineer with expertise in investigation, design, construction, and operation of dams.

Evaluation

40. Most agencies emphasize checklists; however, the Los Angeles Flood Control District uses a rating system. Since none of the procedures reviewed appears to be repeatable, no appropriate overall rating system was found that may be directly used for periodic maintenance of concrete/masonry dams and canals.

41. None of the sources recommends any computer approach for data collection. However, some agencies require the expertise of a trained engineer or a person with technical knowledge to perform inspections. Only four organizations use manuals: the SEED Program of the Bureau of Reclamation, the Ohio Department of Natural Resources, the Colorado Division of Water Resources, and the Pacific Gas & Electric Dam Program.

42. Table 1 illustrates the evaluation of maintenance procedures of the sources.

PART III: ROCK AND EARTH DAMS

43. Information about the maintenance of rock and earth dams was obtained from the following organizations: U.S. Army Corps of Engineers Nashville District, Bureau of Reclamation, Resources Agency of California, Ohio Department of Natural Resources, Virginia Bureau of Water Control Management, North Carolina Department of Natural Resources, Pennsylvania Department of Environmental Resources, Colorado Division of Water Resources, and Kansas Division of Water Resources. The following sections provide details about specific procedures conducted at these sites. Appendix B provides example checklists and computer output for rock and earth dams.

Maintenance Inspection Procedures

U.S. Army Corps of Engineers

44. The Nashville District's maintenance manual includes a section on rock and earth fill dams (Ref. 18). Weekly visual observations are recommended for embankments and fills. Similarly, berm areas must be inspected weekly to check for irregularities such as caving, scour, erosion, seepage, settlement, burrowing animals, and need for mowing. Other areas of inspection include checking for erosion, slides, settlement, springs, boils, and other unusual conditions. Embankments and fills should be checked annually to detect leaks, settlement, excessive erosion, slides, lack of vegetation cover, and deterioration.

45. The maintenance program uses a checklist, manual, computer, and time schedule, but it requires some technical knowledge.

46. The manual contains a comprehensive maintenance task analysis that assigns an inspection routine to each task (Ref. 26). The tasks have been computerized, with four maintenance reports generated:

- a. Maintenance work history (work and cost required to maintain items in the system).
- b. Maintenance inspection report (items to be inspected and the date of inspection).
- c. Delinquent report (items not inspected at the established time).
- d. Maintenance summary report (labor required to maintain the items in the system).

Figure B1 shows examples of these four reports. Although this particular output applies to locks, the same type of report can be produced for rock and earth dams.

Bureau of Reclamation

47. The Bureau of Reclamation's RO&M Program has developed a checklist (Figure B2) for earth dams (Refs. 8,32). The RO&M maintenance procedures also require photographs and a technical report from a professional engineer. The Bureau's SEED Program also has a checklist for earth dams (Figure B3) (Ref. 34). These procedures use photographs and require a professional engineer.

Resources Agency of California

48. The Resources Agency of the State of California uses an inspection report for the San Luis Dam (Ref. 31); however, when compared with other checklists, the basic areas of inspection are quite similar. Dam condition is rated as requiring improvement, substandard condition, or standard condition.

49. The inspection form requires detailed inspection and photographs, but there is no manual that pertains directly to the facility. Generally, the dam and its related structures are inspected twice a year. Figure B4 illustrates the inspection form.

Ohio Department of Natural Resources

50. To provide for safe dams, dikes, and levees, the Ohio Department of Natural Resources (ODNR) has developed the Operation Maintenance and Inspection Manual (Ref. 20). The publication is designed to help owners maintain, operate, and inspect their facilities. It is nontechnical and easy to understand. Although emphasis is on the maintenance of small earth dams, the information can be applied to all types and sizes of dams as well as to dikes and levees. The sections that apply directly to small earth facilities are failure and emergency action, maintenance of embankments, and operation, inspection, and maintenance checklists.

51. The failure and emergency action section describes overtopping, seepage, and structural failures. This section also provides a step process for owners to follow in case of an emergency. The section on maintenance of embankments discusses and, in most cases, illustrates typical vegetation,

erosion, seepage, cracks, slides, settlement, rodent control, and monitoring devices. The operation section discusses lake drains, reservoir levels, recordkeeping, winterizing techniques, vandalism, design modifications, sedimentation and dredging, and low-head dams. The manual also provides basic instructions and a form for recording operation, maintenance, rainfall, and pool-level records.

52. The last section of the manual provides maintenance checklists. ODNR encourages owners to visually inspect their facilities thoroughly at least twice a year. The forms provided should help with inspection tasks. Although use of the checklists is not mandatory, the forms are used by the dam inspection section of the ODNR, and their use by owners is encouraged.

53. The dam inspection checklists include embankments, dikes and levees, and miscellaneous areas. They require observations by an inspector and specification of any required action. There is space for general comments, sketches, and field measurement. Although these checklists provide a thorough examination of dams during inspection, no rating system has been established. Figure B5 illustrates each type of checklist.

Virginia Bureau of Water Control Management

54. The Virginia Bureau of Water Control Management has compiled the pamphlet Safety Evaluation of Small Earth Dams (Ref. 35). The booklet presents general guidance to owners for inspecting and maintaining their structures. Although the information sets forth common problems, it is not intended to cover every type of condition, situation, or emergency that could render a facility unsafe. It also illustrates a "problem" dam and a "sound dam."

55. The pamphlet provides very basic information, with illustrations, about various types of dams and their principal parts, supplies information about inspection procedures, and furnishes checklists. The wording of the checklist (Figure B5) is general so that it can be applied to as many different facilities as possible, including the embankment, principal spillway, emergency spillway, reservoir area, downstream channel, watershed area, and the downstream region. A "yes" or "no" answer is required for all questions, and there is space for the inspector's comments. Maintenance tips are also supplied for each topic addressed by the questions.

56. The pamphlet also discusses maintenance priorities, stressing ongoing upkeep of the facilities. The outline for maintenance priorities is: what needs to be done at once, what needs to be done within the next year, and what needs to be done on a continuing basis. The last section of the pamphlet provides forms for recording dam history and inspections.

57. Safety Evaluation of Small Earth Dams tells how to evaluate the safety of a small earth dam and makes owners aware of general aspects of preventive maintenance. It can be understood easily by the layman. The checklists cover the major areas of dam maintenance, but there is no rating system.

North Carolina Department of Natural Resources

58. The North Carolina Department of Natural Resources and Community Development may inspect any dam at any time upon the request of any affected person or agency or upon a motion of the Environmental Management Commission. Therefore, it must assemble data needed to properly review and study the design and construction of dams, reservoirs, and appurtenances.

59. Dams should be examined every 2 or 5 years, depending on the particular type of construction. The department's Dam Safety section has developed a checklist (Figure B7) for inspecting earth dams, concrete dams, and spillways (Ref. 19). The checklist provides for recording information about different parts of the facility and allows space for comments. The inspectors use this information to complete a followup inspection report. The form does not contain a rating system and there is no manual.

Pennsylvania Department of Environmental Resources

60. The Pennsylvania Department of Environmental Resources has developed an inspection checklist to be used annually (Ref. 1). The facility owner uses the form to do a comprehensive visual examination, with photographs, that will provide the Department with information about the facility's condition.

61. The visual inspection forms (Figure B8) that apply to earth dams include embankment, reservoir and water shed, downstream channel, and instrumentation. The embankment section includes observation of cracks, movement, sloughing or erosion, crest alignment, riprap failure, seepage, drains, and junction of structures. The reservoir and watershed portion

provides recommendations on slopes, sedimentation, and watershed description. The downstream channel section includes observations and recommendations on condition, obstructions or debris, slopes, and population. The instrumentation section gives recommendations or remarks on monumentation, observation wells, weirs, and piezometers.

62. The checklist provides a subjective evaluation of dams, along with illustrative photographs. There is no rating system. However, the final report should indicate plans for correcting any deficiencies indicated by the inspection.

Colorado Division of Water Resources

63. The Colorado Division of Water Resources has developed the Dam Safety Manual (Ref. 5) to provide specific guidance for maintaining a safe dam, avoiding costly repairs, and prolonging facility life.

64. The manual covers fundamental dam components, visual inspection, seepage, upstream slope, crest, downstream slope, outlet system, spillways, concrete dams, monitoring and instrumentation, maintenance, standard operating procedures, emergency plans, and Colorado law.

65. The chapter on dam fundamentals diagrammatically illustrates the various facility components and defines or discusses each one. This is an informative section for personnel who are not very familiar with dams.

66. The section dealing with visual inspection includes a checklist (Figure B9) and itemizes the equipment needed and its use.

67. The chapters on seepage, upstream slope, crest, downstream slope, outlet system, and spillways all have the same format. Several problems that commonly occur are described. There is a diagram or photograph of the problem, a description of the harm resulting from the problem and its causes, and corrective action needed. Figure B9 is an example. It is interesting to note that most actions require an engineer.

68. The chapter on concrete dams covers problems associated with concrete dams. This includes structural cracks, foundation weakness, cracks at construction joints, shrinkage cracks, and deterioration from spalling.

69. The presentation on monitoring and instrumentation provides descriptions and diagrams of monitoring devices. Special forms are included for recording measurements from drains, seepage and wet areas, and observation wells (Figure B9).

70. The chapter on dam maintenance includes methods for tree, brush, and weed control, earth placement, repair of rodent damage, filling in minor cracks, sealing reservoir basins, and rodent control.

71. The section on standard operating procedure presents activities schedules for high-hazard, moderate-hazard, or low-hazard dams.

72. The emergency plan chapter gives owners a written procedure to follow in case of an emergency. It lists potential problems and immediate actions to be taken if these problems occur. It also provides four forms to help owners prepare an emergency plan. The last chapter covers Colorado laws that relate to dams.

73. This manual can be understood easily by the layman. It has a checklist, but does not contain a rating system.

Kansas Division of Water Resources

74. The Water Structures Section of the Kansas Division of Water Resources has developed a checklist for dams that is patterned after the Corps of Engineers National Dam Inspection Program (Ref. 16). The checklist requires the inspector to comment on engineering and construction data as it is considered. The checklist (Figure B10) is divided into three sections: earth embankments, instrumentation, and reservoir. The drawbacks of this system are that the observations are subjective, and there is no rating system.

Other agencies and publications

75. Safety of Existing Dams is a 1983 publication of the National Academy of Sciences (Ref. 36). It includes a failure mode evaluation matrix for embankment dams (Figure B12) that includes slope failure, seepage, foundation movement, unprotected slopes, uplift, undermine, spillways, gates and hoists, obstructions, vandalism, outlet works, piping, and landslides.

76. The evaluation matrix also includes a tabulation of defects, possible indicators, possible causes, effects, and potential remedial measures associated with each failure mode. This type of information may be valuable when developing evaluation techniques.

Evaluation

77. Table 2 provides a comprehensive evaluation, in matrix form, of the maintenance procedures for rock and earth dams. None of the manuals and checklists used will completely fill the needs of a comprehensive maintenance program for rock and earth dams because none has a numerical rating system. It is also questionable whether the maintenance checklists are repeatable.

PART IV: SPILLWAYS, STILLING BASINS, AND OUTLET WORKS

78. Spillways and outlet works are generally inspected as part of the overall dam inspection process. This chapter discusses procedures used for those facilities by the following agencies: U.S. Army Corps of Engineers, Tennessee Valley Authority (TVA), Bureau of Reclamation (RO&M and SEED), Pacific Gas & Electric (PG&E), North Carolina Department of Natural Resources, Pennsylvania Department of Environmental Resources, Colorado Division of Water Resources, Kansas Division of Water Resources, Ohio Department of Natural Resources, and Virginia Bureau of Water Control Management. Appendix C provides example checklists for spillways, stilling basins, and outlet works.

Maintenance Inspection Procedures

79. Information about maintenance programs was obtained from several Corps of Engineers districts (Nashville, Omaha, Portland/Walla Walla, and Rock Island) and the Office of the Chief of Engineers.

80. The Nashville District and the Portland/Walla Walla Districts* have computerized maintenance programs. However, neither program has a rating system that can be applied to the maintenance task components.

81. The variety and scope of the submitted formats shows that there are several levels of sophistication among the districts, ranging from simple checklists to comprehensive computer tracking systems. However, none of these maintenance procedures has a rating component

Nashville District

82. The Nashville District has developed an extensive program that includes a detailed manual from the Operations Division of the Hydro-Power Branch (Ref. 18). This publication, which specifically addresses the maintenance of spillways and outlet works, consists of a comprehensive maintenance task analysis with an inspection routine assigned to each item. However, the manual appears to assume that the operator has a working

*The Portland and Walla Walla Districts use the same procedures and forms, and are considered together for this discussion.

knowledge of the various tasks, malfunctions, states of repair, etc. The maintenance tasks have been computerized and four different maintenance reports are generated (Figure B1). The output is a very useful management tool for the allocation of personnel and cost, but the results neither reflect the state of deterioration nor prioritize items in the system. However, each item does have a maintenance notification card that lists the service required and the various codes, and provides space to record the inspection date and manpower commitment per job. It appears that all items are weighted equally and are repaired on an ongoing or as-needed basis.

Portland/Walla Walla District

83. Data for the Portland/Walla Walla District is similar to that of the Nashville District. They both use a project management data card system to maintain multipurpose and flood control projects (Ref. 27). Each card contains detailed descriptions, functions, and requirements for the piece of equipment being considered. A handwritten record is kept of each item on the preventive maintenance inspection and trouble report.

Omaha District

84. The Omaha District requires a technical report on the facility's condition that includes photographs, interviews, notes, and data from monitoring devices. The observer must first establish an individual checklist for each specific site. Using information from the checklist, an engineer then finishes the report, which includes a descriptive section evaluating the overall condition and an opinion about the immediacy of repair. The report also suggests possible remedial measures. A general guideline provides questions to be answered (Ref. 6).

Rock Island District

85. The Rock Island District has developed an inspection checklist for the spillways and outlet works on the Mississippi River under its jurisdiction (Ref. 33). The form has space for, and requires a comment on, each item. Figure C1 shows a questionnaire used specifically for the Saylorville Dam.

86. No manual or suggested procedure accompanies the checklist, so the type of support provided to ensure consistent judgment and repeatability of the inspection process cannot be determined.

HQUSACE

87. The information provided by HQUSACE does not include a rating system, but does list the components that must be checked and conditions that should be monitored (Ref. 28). Also included is a tabulation of engineering data that might be considered in any investigative report. Specifically, the report presents detailed instructions for inspecting spillways and calculating safety factors for dams (Figure A2).

Evaluation

88. All these organizations use checklists, but none uses a rating system. Table 3 gives an evaluation of the maintenance procedures of each agency or system.

PART V: LOCKS, LOCKWALLS, LOCKGATES, AND OPERATING EQUIPMENT

89. Four districts of the U.S. Army Corps of Engineers (Nashville, Portland, Walla Walla, and Rock Island) supplied information about maintenance programs for locks and associated facilities. The following sections provide detailed descriptions and/or checklists. Appendix D provides example checklists and information for lock walls, lockgates, and operating equipment.

Maintenance Inspection Procedures

Nashville District

90. The Operations Division of the Nashville District's Hydro-Power Branch has developed an extensive maintenance program that includes a detailed manual (Ref. 18). While the manual addresses the maintenance of dams (concrete, earth, and rockfill) and the associated equipment, the sample computer output studied is specifically for the Watts Bar Lock.

91. The program, which consists of a comprehensive maintenance task analysis, assigns an inspection routine to each task. However, the program appears to assume that the operator has a working knowledge of the various tasks, malfunctions, states of repair, etc. (Examples include: "Repair as necessary," "Do test," and "Maintain as required.") Tracking of these tasks has been computerized, and four different maintenance reports (Figure B1) are generated.

92. The output is a very effective management tool for allocating personnel and funds. Nevertheless, the results neither indicate the state of deterioration nor prioritize the items within the general maintenance system. Each item has a maintenance notification card that lists the services needed, the various codes, and a record of the inspection date and manpower commitment per job. All items appear to be weighted equally, and repairs are performed on an ongoing or as-needed basis.

93. The maintenance components in the Nashville plan include:
- a. Checklist.
 - b. Manual.
 - c. Computer application.

d. Requirement of technical knowledge.

e. Time schedule.

Portland/Walla Walla Districts

94 The Portland/Walla Walla Districts generate data similar to that of the Nashville District. The sample computerized output considered for this study includes that generated for a lock network (Ref. 27). For example, items of repair associated with locks listed on the computer output show that a navigation lock staff gage was replaced, a handrail was painted, and a tainter valve was restored. The districts use a project management data card system; each card contains detailed descriptions, functions, and requirements for the equipment involved. A handwritten record for each item documents the preventive maintenance, inspection, and trouble reports investigated. Computerized output is also available that indicates the particular maintenance shop charged, the associated cost, and the manpower hours. Figure D1 gives a sample output list.

95. The Walla Walla District also has a system in which a 15-person inspection team performs a thorough structural investigation every 5 years. Their findings are published as an extensive technical report.

Rock Island District

96. The Rock Island District does not have a computerized approach, but does use an inspection checklist (Figure D2) for the locks and dams on the Mississippi River under its jurisdiction (Ref. 33). The documentation allows space for the inspector to comment on each item. These items include approach walls, lock walls, miter gates, and tainter valves, and they are evaluated by the condition and alignment of structural concrete, wall joints, and other general details. Gate valves, seals, and operating equipment are also considered.

Evaluation

97. The Nashville District and the Portland/Walla Walla Districts have developed very sophisticated computerized maintenance programs. While their formats are different, both approaches address similar items and generate typical information for tracking costs and managing manpower.

98. The Portland/Walla Walla and Rock Island Districts provided illustrative formats without supplementary documentation. The Sample Program Management cards indicate the amount of technical knowledge needed to perform the required maintenance tasks, the suggested frequency of inspection and the degree of repeatability. Of the systems reviewed, the card system of the Portland/Walla Walla Districts provides the most extensive and practical task analysis for equipment maintenance; however, a rating system is not used.

99. Table 4 gives a comprehensive evaluation, in matrix form, of the maintenance procedures for lock walls, lock gates, and operating equipment. Since there is no numerical rating system and it is questionable whether the results are repeatable, the checklists will not be adequate for a comprehensive maintenance program for locks, lockwalls, lockgates, and operating equipment.

PART VI: POWERHOUSES AND PUMPING PLANTS

100. A review of the literature concerned with powerhouse and pumping equipment and with instrumentation indicates that there are no specific maintenance programs for this category. However, these components are included as peripheral items to other facilities such as dams and locks.

101. The American Society of Civil Engineers (ASCE) has published an article (Ref. 21) on the operation and maintenance of irrigation and drainage systems. The components discussed include pumps and minor mechanical, electrical, and hydraulic equipment.

102. This chapter discusses procedures used for powerhouses and pumping plants by the U.S. Army Corps of Engineers, the Bureau of Reclamation, the Los Angeles Flood Control District, the Kansas Division of Water Resources, and the Federal Emergency Management Agency. The following sections provide detailed descriptions and/or checklists. Appendix E provides example checklists and computer output for powerhouses and pumping plants.

Maintenance Inspection Procedures

U.S. Army Corps of Engineers

103. Nashville District. The Nashville District's Operations Division of the Hydro-Power Branch has an extensive program that includes a detailed manual (Ref. 18) which addresses the maintenance of equipment associated with dams and outlines a maintenance task analysis and inspection routine for each item. However, these procedures assume that the operator comprehends the various tasks, existing malfunctions, states of repair, etc. Examples include: "Repair as necessary," "Do test," "Maintain as required." These tasks are tracked by computer, and four maintenance reports (Figures B1 and E1) are generated:

- a. Maintenance work history (work and cost required to maintain items in the system).
- b. Maintenance inspection report (items to be inspected and the date).
- c. Delinquent report (items not inspected at the established time).
- d. Maintenance summary report (labor required to maintain the items in the system).

104. This output appears to be a useful management tool for allocating personnel and funds, but the results neither reflect the state of deterioration nor prioritize items within the system. However, a maintenance notification card for each item tabulates recorded inspection dates and the cumulative manpower commitment per job. Figure E2 shows a maintenance notification card for switchboards. It appears that all items are weighted equally and are repaired on an ongoing or as-needed basis.

105. Portland/Walla Walla Districts. The Portland/Walla Walla Districts generate about the same information as the Nashville District. They have compiled a detailed inventory that describes each piece of mechanical and instrumentation equipment. To maintain their multipurpose power and flood control projects, these districts use a project management data card system. A handwritten record is kept on each item for the preventive maintenance, inspection, and trouble reports investigated (Figures D1 and E3). A computerized output shows the maintenance shop charged, the cost incurred, and the personnel hours used. The data cards present a comprehensive view of the desired state of each piece of equipment. Components of this system are:

- a. Checklist.
- b. Manual.
- c. Computer application.
- d. Requirement of technical knowledge.
- e. Repeatable.
- f. Time schedule.

106. The Walla Walla District also requires a 15-person team to conduct a comprehensive structural investigation every 5 years. The results are presented in an extensive technical report.

Bureau of Reclamation

107. The Bureau of Reclamation supervises the operation and maintenance of a large number of dams and dikes in the western United States. Checklists have been developed for periodic on-site examination of these structures, but they are not adapted to computer application. The listings include structures such as power facilities and pumping plants and are open-ended so that only knowledgeable personnel can provide the desired feedback.

108. Review of Operation and Maintenance (RO&M) Program. The RO&M Program requires scheduled inspections of all project facilities, including power and pumping plants (Refs. 8, 32). Project and regional personnel examine all major, minor, and special features biannually or triannually. Figure E4 shows the checklist for pumping and powerhouse facilities. There are three categories of recommendations for each item:

- a. Severe deficiencies: immediate action is needed to maintain structural safety or adequate functioning.
- b. Action required to prevent or reduce further damage or an operational error.
- c. Recommendations that are considered useful but less important than those of the first two categories.

109. These recommendations are identified and recorded as follows:

- a. The first two digits indicate the year that the recommendation was made (80).
- b. The third digit indicates one of the three recommendations categories (2).
- c. A letter individualizes each recommendation made (a) (b) (c).

110. The components of this maintenance program are:

- a. Checklist.
- b. Technical evaluation.
- c. Requirement of professional engineer.
- d. Requirement of technical knowledge.
- e. Rating system.
- f. Frequency of inspection.

111. Safety Evaluation of Existing Dams (SEED). The Bureau's program includes checklists for dams and power facilities, but is a guideline rather than a specific maintenance program. This program uses on-site examination and analysis to maintain facility safety (Ref. 34). Checklists are organized like those of the RO&M program. Information for outlet works and power features is included in the checklist (see Figure E5).

112. Checklists are to be used as guides and are not to limit the examination. They can become a permanent part of the Bureau's reference materials. Each checklist is individualized for the specific site, so the general checklist must be kept updated as required.

113. The Bureau's checklists consist of a short outline of information and special instructions for the examination. Sheets must be included for

special items, additional notes, and identification of unique features. Photographs are also taken to maintain an historical record.

114. The components of this maintenance program are:

- a. Checklist.
- b. Manual.
- c. Technical evaluation.
- d. Requirement of professional engineer.
- e. Requirement of technical knowledge.
- f. Frequency of inspection.

Los Angeles Flood Control District

115. The Los Angeles Flood Control District operates and maintains several flood control reservoirs. After the Verdugo Wash Channel failure in September 1983, the district started an emergency program to identify, evaluate, and repair structural deficiencies in the open channel system (Ref. 17). It was concluded that under normal circumstances the structural inspection should be conducted by operations and maintenance field personnel within the framework of the existing maintenance management system. A checklist and a rating procedure have been developed (Figure A5), and a detailed facility monitoring and inspection procedure (Figure A6) is also used.

116. The components of this maintenance program are:

- a. Checklist.
- b. Manual.
- c. Technical evaluation.
- d. Requirement of professional engineer.
- e. Requirement of technical knowledge.
- f. Repeatability.
- g. Frequency of inspection.

The district's checklist and maintenance rating procedures also include care of pumping plants.

Kansas Division of Water Resources

117. The water structures section of the Kansas State Division of Water Resources has patterned its checklist (Figure E6) for dams after the Corps of Engineers' National Dam Inspection Program. The checklist requires comments

on engineering and construction data as the data are examined, and items on the form also address instrumentation (Ref. 16). The observations made in filling out the checklist are subjective.

Federal Emergency Management Agency (FEMA)

118. FEMA does not have any form of checklist or rating system for powerhouses and pumping plants. Nevertheless, they suggest that checklists be prepared for the various structural, electrical, and mechanical features of powerhouses and pumping plants. Also the inspection should be conducted by a licensed professional engineer experienced in the investigation, design, construction, and operation of dams. The recommended frequency of inspection is once every 5 years.

Evaluation

119. Table 5 illustrates, in matrix form, the evaluation of maintenance procedures for powerhouses and pumping plants. Of the programs reviewed, the individual cards used by the Portland/Walla Walla Districts provide the most extensive task analysis for equipment maintenance. Most agencies and publications emphasize checklists, but only the Los Angeles Flood Control District uses a rating system. Since none of the procedures appears to be repeatable, no appropriate rating system was found that applies directly to maintenance of powerhouses and pumping plants.

PART VII: BRIDGES AND ROADS

120. This chapter outlines maintenance programs used by three programs responsible for maintaining roads and highways: the Federal Highway Administration's Bridge Replacement and Rehabilitation Programs, the Corps of Engineers' Pavement Maintenance Management for Roads and Parking Lots (PAVER), and the Indiana Department of Highways manual. The following sections provide details about these programs. Appendix F provides examples for bridges and roads.

Maintenance Inspection Procedures

Federal Highway Bridge Replacement and Rehabilitation Program

121. The Federal Highway Administration developed the Bridge Replacement and Rehabilitation Program for state highway departments to use in rating the condition of bridges and tunnels (Ref. 30). The program uses trained technicians rather than professional engineers to inspect structures. The inspection procedures have been simplified so that different trained technicians who inspect the same bridge would be likely to produce identical evaluations. Thus, the process is repeatable.

122. To determine the condition of a bridge, the technician checks each component of the structure and assigns it a rating number from 0 to 9 (Figure F1). These values are recorded on an inspection checklist. When the inspection is completed, the values are transferred to a computer input sheet. Use of this system requires knowing the bridge's dimensions, which are used to calculate the facility's functional obsolescence and safety. The checklist ratings and dimensions are then considered in calculating the overall sufficiency rating.

123. This is an excellent system that could easily be adapted for rating and maintaining civil works structures and facilities.

Corps of Engineers' Pavement Maintenance Management for Roads and Parking Lots (PAVER)

124. The PAVER system is used to inspect and rate the pavement of roads and parking lots (Ref. 39). The system is designed to help optimize the allocation of pavement repair funds.

125. The first step in the rating procedure is dividing the pavement network into manageable sections. Each section is then further subdivided into sample units. Each unit is given a pavement condition index (PCI) rating related to its structural integrity, structural capacity, roughness, skid resistance, hydroplaning potential, and deterioration rate. The PCI scale ranges from 0 to 100. A separate inspection form is required for each sample unit. Nineteen different distress types may be used in assigning the PCI value. In each pavement section, the type, diversity, severity, and the PCI reduction number are determined and recorded.

126. The overall PCI may be computed by subtracting the sum of the reductions from 100. The deterioration rate can also be determined by placing this value along with the PCI from previous years on a PCI-versus-time graph.

127. This system provides for a repeatable procedure for rating road condition. A manual is available that contains a series of photographs representing examples of high-, medium- and low-severity pavement distress.

128. Figure F2 shows an example of the PCI scale and condition rating and illustrates the computer output for PAVER.

Indiana Department of Highways

129. The Indiana Department of Highways' publication, Development and Use of a Management Information System to Identify Areas of Routine Maintenance Productivity Improvement was reviewed (Ref. 38). The review did not investigate the methods used to rate or check the condition of roads and bridges. Instead, it dealt with the results of studies performed to analyze fund distribution methods. Findings pertinent to this investigation that may be used during the development and operation of a comprehensive maintenance management system were as follows:

- a. In a study performed by the Pennsylvania Department of Transportation, an inverse relationship was found between efficiency and quality of work.
- b. Specific maintenance actions are rarely consistently recommended following a report of specific problems.
- c. Although the amount of money spent on repairs increases with the number of lane-miles, the relationship is not directly proportional.

Evaluation

130. Table 6 is an evaluation matrix of the maintenance procedures for bridges and roads. Both the Federal Highway Administration and PAVER have a systematic, repeatable rating system. They also both have an exceptional range of qualities that may be useful for developing an overall maintenance management system for bridges and roads.

PART VIII: MISCELLANEOUS FACILITIES

131. Because of the variety of miscellaneous facilities investigated, evaluations were made on the merits of each program rather than in reference to a particular facility type (Refs. 3, 11, 12). Organizations involved included the Training and Doctrine Command (TRADOC), the Forces Command (FORSCOM), Southwestern Division of the U.S. Army Corps of Engineers, and the Resources Agency of the State of California. The following sections summarize each organization's procedures. Appendix G provides example checklists and information for miscellaneous facilities.

Maintenance Inspection Procedures

TRADOC's BMAR and DMAR Rating Systems

132. The purpose of TRADOC'S BMAR (Backlog of Maintenance and Repair) and DMAR (Deferred Maintenance and Repair) rating systems is to facilitate the distribution of available funds for maintenance and repair projects on U.S. Army installations (Refs. 2, 42).

133. Both systems involve the following steps:

- a. Compilation of necessary information for a project by an installation officer.
- b. Verification of the project by a TRADOC validator.
- c. Decision on funding: the TRADOC score and the existing design status are the two items used to determine the funding ratio among competing projects. The TRADOC score, which is assigned by the TRADOC validator, reflects the project's overall degree of need. The design status is a statement of the condition of readiness to begin work on the project.

134. For BMAR, the scoring is determined by the following five major groups:

- a. Functional use of the facility.
- b. Justification factors related to maintenance and repair.
- c. Type of project (choose one of the following):
 - (1) Buildings and grounds.
 - (2) Utilities.
- d. Condition of the facility.
- e. Priority assigned by the installation.

135. For DMAR, the scoring is determined by the following five major groups:

- a. Category of family housing.
- b. Category of requirement.
- c. Type of work.
- d. Condition of the facility.
- e. Priority assigned by the installation.

136. Each of the five major groups in both BMAR and DMAR are further divided into areas that are assigned a numerical rating between 1 and 10. Figure G1 gives an example of this detailed breakdown.

137. The ratings obtained from the first four groups in both BMAR and DMAR are added to obtain the "base score." The sum of the "base score" and the rating value calculated from the project's priority is multiplied by 1000 to obtain the "TRADOC score."

138. The rating value is obtained from an expression that alters the assigned priority number so that a priority of 1 translates to a rating value of 10, and those with second, third, etc., priority numbers receive rating values that are progressively less than 10. Figure G2 gives a sample listing of some BMAR project ratings and scores.

FORSCOM Regulation 420-3

139. The purpose of FORSCOM Regulation 420-3 is to set priorities on maintenance and repair projects for all FORSCOM installations and subinstallations. The FORSCOM procedure includes three main steps (Refs. 10, 15):

- a. The installation lists its maintenance and repair projects. Then reports, which include a general information sheet and a rating worksheet for each project, are sent to the FORSCOM authorities.
- b. A FORSCOM Technical Service Division representative visits the installation, reviews the project priority system used, and decides whether to approve it. A spotcheck of all project documents is also made.
- c. A decision is made on funding. Funding is based on several items, including the following:
 - (1) FORSCOM's priority score. Besides its own priority score, FORSCOM will also consider the priority given to the project by the installation.

- (2) Results from FORSCOM's field reviews.
- (3) The project status. The project status indicates the ability to design and/or obligate funds for the project during the current fiscal year.

140. The project rating system recommended by FORSCOM is divided into five categories:

- a. Facilities use factor.
- b. Project purpose factor.
- c. Project type factor.
- d. Mission factor.
- e. Condition factor.

141. Each factor is further subdivided into functional areas which are assigned a rating range that varies from eight to ten. Figure G3 provides additional details. An intermediate score is then obtained by adding all the rating values from the five categories. The final score for the project is determined by adding the intermediate score to the priority rating score and multiplying the sum by 1000.

142. The priority rating score is obtained by an expression which alters the assigned priority number so that a priority of 1 gets a score of 10, and those with second, third, etc., priorities get values that are progressively less than 10.

U.S. Army Corps of Engineers, Southwestern Division

143. The Southwestern Division has submitted a proposal for a project operation and maintenance funding level matrix (Ref. 22). Since this appears to be an application of global program development and justification rather than a specific itemization of maintenance procedures, considerable modification may be necessary for it to be useful for civil works projects. Figure G4 is a sample entry of this matrix.

The Resources Agency of the State of California

144. The Resources Agency of the State of California has developed inspection reports for operation and maintenance of aqueducts and dams based on the following rating system (Ref. 31):

- a. P: Poor quality
- b. G: Good quality

- c. E: Excellent quality
- d. N.C.: No change in quality

145. Figure G5 shows an example of this procedure. Photographs and specific remarks are also required. Generally, headquarters personnel inspect the aqueducts about once a year. However, dams and related structures are usually inspected twice a year. This procedure involves, in part, a general checklist. However, except for dams, the checklists do not have a comprehensive rating system.

Evaluation

146. Table 7 illustrates, in matrix form, the evaluation of maintenance procedures for miscellaneous facilities. TRADOC and FORSCOM maintenance and repair funding programs use basically the same procedures with some minor internal differences. Both deal with the maintenance and repair of facilities on U.S. Army installations. Each uses a numerical rating system that helps compare projects. Actual rating procedures appear to be repeatable if the raters are experienced and have completed a comprehensive training course. Therefore, both systems appear to offer approaches that, with modification, may be applicable for developing a comprehensive maintenance management program.

PART IX: CONCLUSIONS

147. This report has described and evaluated various maintenance procedures related to several civil works (type) structures and facilities. Most of the procedures studied for this research include the use of checklists for maintenance and review operations. However, TRADOC, FORSCOM, and FEMA do not use the checklist format. Twelve agencies have developed manuals and/or explanatory materials for maintenance systems. Various other rating systems are used by eight sources. Most of the rating systems evaluate facilities according to the following categories: yes/no, satisfactory/unsatisfactory, high/medium/low, excellent/good/fair/no change/bad/critical, etc. Five sources use a computer data bank to assist in maintenance operations, and eight sources require the use of photographs in technical evaluations.

148. Sixteen sources require professional engineering and technical knowledge to conduct maintenance evaluations. The structures which need professional engineering services and/or technical knowledge for maintenance and inspection include spillways, stilling basins, rock and earth embankments, shore and bank stabilization, bridges, lockwalls and gates, powerhouse equipment, and various miscellaneous facilities. Repeatable systems also generally require extensive training and explanatory guidelines. Only four systems were found to be repeatable.

149. For most maintenance systems, it is vital to have a time schedule or an overall frequency of inspection plan. Fifteen sources were found to inspect their facilities at specific time schedules.

150. No specific or uniform pattern was observed among the procedures studied that can be used as a general guideline for civil works maintenance. The facilities differ markedly in their nature, purpose and use, amount and type of building material, geographical location, environmental and geological condition, and physical, mechanical, engineering, and architectural aspects. Therefore, no appropriate overall rating system was found to apply directly to the periodic maintenance of civil works structures, and no system appeared to be easily usable and reliable when used by inexperienced raters. However, the Corps of Engineers' PAVER and the Federal Highway Bridge Inspection Program appear to offer approaches that, with modification, may be applicable to certain types of civil works structures.

REFERENCES

1. Annual Inspection by Owners (Pennsylvania Department of Environmental Resources, Harrisburg, Pennsylvania, 1984).
2. BMAR Field Book, Department of the Army, Training and Doctrine Command, (TRADOC) (Engineering Division, 1984).
3. Brown, Jack, "The Preventive Maintenance Planning Guide," Plant Engineering (March 8, 1984), pp 151-153.
4. Buttrey, H. C. and D. T. Tanner, TVA's Inspection and Maintenance Program, Tennessee Valley Authority (TVA) (Knoxville, Tennessee, 1979).
5. Dam Safety Manual (Colorado Division of Water Resources, Engineer's Office, Denver, Colorado, June 1983).
6. Dams and Public Safety (Omaha District, U.S. Bureau of Reclamation, 1980).
7. Evaluation of Dam Safety (American Society of Civil Engineers [ASCE], December 1976).
8. Examination Report, Medicine Creek and Red Willow Dams (U.S. Bureau of Reclamation, Engineering and Research Center, Denver, Colorado, July 1983).
9. Federal Guidelines for Dam Safety (Federal Emergency Management Agency, June 25, 1979).
10. FORSCOM Regulation 420-3 (U.S. Army Forces Command, March 1, 1984).
11. Herbaty, Frank, Cost-Effective Maintenance Management (Noyes Publications, Park Ridge, New Jersey, 1983).
12. Herbaty, Frank, "Maintenance Management System, Parts I-IV," Plant Engineering (October 14, 1976).
13. Hoyt, William G. and Walter B. Langbein, Floods (Princeton University Press, Princeton, New Jersey 1955).
14. Inspection, Maintenance and Rehabilitation of Old Dams (ASCE, 1973).
15. Integrated Facilities System User's Manual (Department of the Army, Fort Lee, Virginia, April 1981).
16. Kansas State Board of Agriculture, Division of Water Resources, Dam Evaluation Checklist.
17. Los Angeles Flood Control District Checklist, Los Angeles, California.

18. Maintenance Manual (Nashville District, Operations Division, Hydro-Power Branch, U.S. Army Corps of Engineers, November 1972).
19. North Carolina Administrative Code (Dam Safety) Department of Natural Resources and Community Development (Raleigh, North Carolina, November 1982).
20. Operation, Maintenance and Inspection Manual for Dams, Dikes, and Levees (Ohio Department of Natural Resources, Division of Water, Dam Inspection Section, November 1983).
21. Operation and Maintenance of Irrigation and Drainage Systems, American (ASCE, 1973).
22. Operations, Maintenance and Precautions, Appendix C-2 (Southwestern Division, U.S. Army Corps of Engineers, April 1983).
23. Pacific Gas and Electric, Bulletin No. 55 (PG&E, San Francisco, California, April 1, 1975).
24. Pacific Gas and Electric, Bulletin No. 63 (PG&E, San Francisco, California, March 15, 1979).
25. Pazwash, H., "Qanats," Civil Engineering (ASCE, March 1983).
26. Preventive Maintenance System (Computer Output), U.S. Army Corps of Engineers, Nashville District (March 1983).
27. Project Management Computer System Output (Portland/Walla Walla Districts, U.S. Army Corps of Engineers, 1983).
28. Recommended Guidelines for Safety Inspection of Dams (Office of the Chief of Engineers, Department of the Army, 1972).
29. The REMR Notebook, with periodic supplements (U.S. Army Corps of Engineers, Waterways Experiment Station, Vicksburg, Mississippi, 1986).
30. Replacement and Rehabilitation Manual (Federal Highway Administration, Washington, D.C., 1982).
31. Resources Agency Checklist (Department of Water Resources, Sacramento, California, Checklist, 1984).
32. Review of Operation and Maintenance Program (U.S. Bureau of Reclamation, Denver, Colorado, March 1982).
33. Rock Island District, U.S. Army Corps of Engineers Checklist (Department of the Army, Rock Island, Illinois).
34. Safety Evaluation of Existing Dams (U.S. Bureau of Reclamation, U.S. Department of the Interior, Denver, Colorado, June 1983).

35. Safety Evaluation of Small Earth Dams (Virginia State Water Control Board, Bureau of Water Control Management, Richmond, Virginia, January 1983).
36. Safety of Existing Dams, National Academy of Science Press (NASP, 1983).
37. Safety of Small Dams (ASCE, 1974).
38. Sanderson, V. A. and K. C. Sinha, Development and Use of a Management Information System for Production Improvement (Indiana Department of Highways, Indianapolis, Indiana, 1984).
39. Shahin, M. Y. and S. D. Kohn, Pavement Maintenance Management for Roads and Parking Lots, Technical Report M-294/ADA110296 (U.S. Army Construction Engineering Research Laboratory, Champaign, Illinois, 1981).
40. Tennessee Valley Authority (TVA), Checklists (Tennessee Valley Authority, Knoxville, Tennessee).
41. Thomas, Henry H., The Engineering of Large Dams, Part I and Part II (John Wiley and Sons, New York, 1976).
42. TRADOC Regulation No. 420-3 (U.S. Army Training and Doctrine Command, Fort Monroe, Virginia, December 1981).
43. Tschantz, B. A., Report on Review of State Non-Federal Dam Safety Programs (Federal Emergency Management Agency, February 28, 1983).

Table 1

Summary of Existing Maintenance Procedures for Concrete/Masonry Dams

Procedures Code List	Pennsylvania Department of Environmental Resources	Colorado Division of Water Resources	Kansas Division of Water Resources	Pacific Gas & Electric Company	Federal Emergency Management Agency	Operation & Maintenance of Irrigation & Drainage Systems	The Engineering of Large Dams	Safety of Existing Dams	U. S. Army Corps of Engineers (Omaha District)	U. S. Army Corps of Engineers (Office of Chief Engineer)	Bureau of Reclamation (R O & H Program)	Bureau of Reclamation (SEED Program)	Los Angeles Flood Control District	Tennessee Valley Authority	Ohio Department of Natural Resources	North Carolina Department of Natural Resources
1. Checklist	/	/	/	/			/	/	/	/	/	/	/	/	/	/
2. Manual (explanatory)		/		/								/			/	
3. Rating System													/			
4. Computer Application																
5. Technical evaluation w/o photographs									/		/	/		/		
6. Requires professional engineer				/		/	/		/	/	/	/		/		
7. Requires technical knowledge						/	/		/		/	/		/		
8. Repeatability																
9. Frequency of inspection	/			/		/	/				/	/		/	/	

Table 2
Summary of Existing Maintenance Procedures for Rock and Earth Dams

Procedures Code List	U. S. Army Corps of Engineers Nashville District	U. S. Army Corps of Engineers Rock Island District	Bureau of Reclamation R O & M Program	Bureau of Reclamation SEED Program	Resources Agency of California	Ohio Department of Natural Resources	Virginia Bureau of Water Control Management	North Carolina Department of Natural Resources	Pennsylvania Department of Environmental Resources	Colorado Division of Water Resources	Kansas Division of Water Resources	Operation & Maintenance of Irrigation & Drainage Systems	Safety of Small Dams	Safety of Existing Dams (NASP)
1. Checklist	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓		✓	✓
2. Manual (explanatory)	✓			✓		✓	✓			✓				✓
3. Rating System														
4. Computer Application	✓													
5. Technical evaluation w/o photographs			✓	✓										✓
6. Requires professional engineer			✓	✓									✓	✓
7. Requires technical knowledge	✓		✓	✓									✓	✓
8. Repeatability														
9. Frequency of Inspection	✓		✓	✓	✓			✓	✓					

Table 3
Summary of Existing Maintenance Procedures for Spillways, Stilling Basins, and Outlet Works

Procedures Code List	U. S. Army Corps of Engineers Nashville District	Portland District	Omaha District	Rock Island District	HQUSACE	Bureau of Reclamation R O & M Program	Bureau of Reclamation SEED Program	Tennessee Valley Authority	Pacific Gas & Electric	Safety of Small Dams	Safety of Existing Dams	Ohio Department of Natural Resources	Virginia Bureau of Water Control Management	North Carolina Dept. of Natural Resources	Pennsylvania Dept. of Environmental Resources	Colorado Division of Water Resources	Kansas Division of Water Resources
1 Checklist	/	/	/	/		/	/	/	/			/	/	/	/	/	/
2. Manual (explanatory)	/	/					/		/			/	/			/	/
3. Rating System																	
4. Computer Application	/	/															
5. Technical evaluation w/o photographs			/			/	/										
6. Requires professional engineer		/				/	/		/								
7. Requires technical knowledge	/	/				/	/										
8. Repairability																	
9. Frequency of Inspection	/	/				/	/	/	/			/				/	/

Table 4
Summary of Existing Maintenance Procedures for Locks,
 Lockwalls, Lockgates, and Operating Equipment

Procedures Code List	U. S. Army Corps of Engineers Nashville District	U. S. Army Corps of Engineers Portland/Valla Walla	U. S. Army Corps of Engineers Rock Island District
1. Checklist	✓	✓	✓
2. Manual (explanatory)	✓	✓	
3. Rating System			
4. Computer Application	✓	✓	
5. Technical evaluation w/o photographs			
6. Requires professional engineer			
7. Requires technical knowledge	✓	✓	
8. Repeatability			
9. Frequency of inspection	✓	✓	

Table 5
Summary of Existing Maintenance Procedures for
Powerhouses and Pumping Plants

Code List Procedures	U. S. Army Corps of Engineers Nashville District	U. S. Army Corps of Engineers Portland/Walla Walla Bureau of Reclamation R O & M Program	Bureau of Reclamation SEED	Los Angeles Flood Control District	Kansas Division of Water Resources	ASCE Publication "Operation & Maintenance of Irr. & Drainage Syst."
1. Checklist	✓	✓	✓	✓	✓	✓
2. Manual (explanatory)	✓	✓		✓		✓
3. Rating System			✓	✓		
4. Computer Application	✓	✓				
5. Technical evaluation w/o photographs			✓	✓		✓
6. Requires professional engineer			✓	✓		✓
7. Requires technical knowledge	✓	✓	✓	✓		✓
8. Repairability						
9. Frequency of inspection	✓	✓	✓	✓		✓

Table 6
Summary of Existing Maintenance Procedures for
Bridges and Roads

Procedures Code List	Federal Highway Administration	PAVER	Indiana Dept. of Highways
1. Checklist	/	/	
2. Manual (explanatory)	/	/	
3. Rating System	/	/	
4. Computer Application	/	/	
5. Technical evaluation w/o photographs		/	
6. Requires professional engineer			
7. Requires technical knowledge	/	/	
8. Repeatability	/	/	
9. Frequency of inspection	/	/	

Table 7
Summary of Existing Maintenance Procedures for
Miscellaneous Facilities

Procedures Code List	TRADOC	FORSCOM	California Aqueduct (Resources Agency)	U.S. Army Corps of Engineers, Southwest Division
1. Checklist			✓	
2. Manual (explanatory)	✓	✓		
3. Rating System	✓	✓	✓	
4. Computer Application	✓			✓
5. Technical evaluation w/o photographs			✓	✓
6. Requires professional engineer				
7. Requires technical knowledge	✓	✓		
8. Repairability	✓	✓		
9. Frequency of inspection			✓	

APPENDIX A: CHECKLISTS AND EXPLANATORY
MATERIALS FOR CONCRETE/MASONRY DAMS

General Guidelines for the Observer. There are so many conditions which might endanger a dam that great care must be taken lest some be overlooked. For this reason, a checklist of questions such as the following should be used.

1. Have changes occurred in the environs of the reservoir that may necessitate reexamination of the design or of the surveillance program (e.g., industrial activities such as deep excavation, trenching, tunneling, building construction, or storage of explosives or flammable materials)?
2. Are there utilities such as oil, water, or sewerlines near or crossing the dam or its appurtenances that would jeopardize safety if they were broken?
3. Are access roads and communication lines to the damsite located and constructed so that they will not be disrupted during extreme emergency?
4. Are the structural analyses of the dam satisfactory, or should new analyses be made using the latest design technology?
5. Is the outlet capacity adequate to lower the reservoir rapidly during an emergency?
6. Is the spillway capable of discharging floodflows projected on the basis of up-to-date hydrological records?
7. Is there danger of spillway discharge undercutting the structure?
8. Are adequate auxiliary power and other redundant systems provided for hoist operation or other requirements during an emergency?
9. Is the spillway channel constructed and maintained so that there will be no dangerous erosion, or debris deposited, in the river channel?
10. Is adequate ventilation provided in shafts, tunnels, and galleries to prevent corrosion and to protect personnel from noxious gases?
11. Is essential machinery operable, especially such items as gates, valves, and hoists?
12. Are drainage sump pumps, if any, operable?
13. Are automatic alarms and telemetering devices functioning?
14. Is riprap, soil-cement, or other revetment intact as constructed?
15. Is all instrumentation in satisfactory working order.

Figure A1. Dams and public safety
(Omaha District, USBR, 1980)

16. Is there vegetation on embankments or abutments that might obscure adverse conditions from the Inspector's view?
17. In the case of concrete dams, is there any reason to doubt the strength of the concrete? Has this been confirmed by nondestructive tests or tests of cores?
18. Are intake works for outlets and spillways free from silt and debris?
19. Are adequate emergency supplies and equipment available for handling adverse situations at the dam?
20. Have operating mechanisms that operate infrequently been checked or exercised to verify that they function properly?
21. Are vulnerable facilities protected against vandalism or sabotage by installation of fencing, locks, and intrusion-detection devices?
22. Are competent, trained personnel assigned to surveillance?
23. Do operations personnel have proper instructions and authority for action to be taken during an emergency?
24. Are piezometer readings and water levels in wells reasonable, steady, and consistent with reservoir height?
25. Are additional piezometers, wells, or weirs necessary for proof of safety?
26. Are reservoir linings, if any, performing as designed?
27. Are surveillance data receiving timely analyses?
28. Has the dam crest settled and thereby reduced the freeboard for flood discharge?
29. Is leakage of water excessive? Is it increasing or decreasing? Is it clear or turbid? Are there large variations in individual drain discharges?
30. Are wet spots visible on the downstream face of the embankment or at abutment groins or immediately downstream?
31. Is there evidence of dissolution of foundation rock by seepage?
32. Is potentially dangerous seepage apparent in the vicinity from sources other than the reservoir, such as in the abutments at high level?
33. Are signs visible of any sloughing or slumping of embankments, abutments, or the reservoir environs?
34. Is piping evident, especially where fills have been placed against or covered by structures?
35. At dams with concrete face slabs, is there visible warping or other distress?
36. Has cracking developed in structures, embankments, or foundations?
37. Are there any signs of erosion of the embankment or its foundation?
38. Has any change occurred in alignment of parapet walls or retaining walls?
39. Has any recent seismic activity been recorded in the area? If so, are there any signs of detrimental effects on the reservoir or its environs?

Figure A1. (Continued)

This appendix provides guidance for performing field inspections and may serve as the basis for developing a detailed checklist for each dam.

1. Concrete Structures in General.

a. Concrete Surfaces. The condition of the concrete surfaces should be examined to evaluate the deterioration and continuing serviceability of the concrete. Descriptions of concrete conditions should conform with the appendix to "Guide for Making a Condition Survey of Concrete in Service," American Concrete Institute (ACI) Journal, Proceedings Vol. 65, No. 11, November 1968, page 905-918.

b. Structural Cracking. Concrete structures should be examined for structural cracking resulting from overstress due to applied loads, shrinkage and temperature effects or differential movements.

c. Movement - Horizontal and Vertical Alignment. Concrete structures should be examined for evidence of any abnormal settlements, heaving, deflections, or lateral movements.

d. Junctions. The conditions at the junctions of the structure with abutments or embankments should be determined.

e. Drains - Foundation, Joint, Face. All drains should be examined to determine that they are capable of performing their design function.

f. Water Passages. All water passages and other concrete surfaces subject to running water should be examined for erosion, cavitation, obstructions, leakage or significant structural cracks.

g. Seepage or Leakage. The faces, abutments and toes of the concrete structures should be examined for evidence of seepage or abnormal leakage, and records of flow of downstream springs reviewed for variation with reservoir pool level. The sources of seepage should be determined if possible.

h. Monolith Joints - Construction Joints. All monolith and construction joints should be examined to determine the condition of the joint and filler material, any movement of joints, or any indication of distress or leakage.

i. Foundation. Foundation should be examined for damage or possible undermining of the downstream toe.

Figure A2. Inspection items (HQUSACE)

j. Abutments. The abutments should be examined for sign of instability or excessive weathering.

2. Embankment Structures.

a. Settlement. The embankments and downstream toe areas should be examined for any evidence of localized or overall settlement, depressions or sink holes.

b. Slope Stability. Embankment slopes should be examined for irregularities in alignment and variances from smooth uniform slopes, unusual changes from original crest alignment and elevation, evidence of movement at or beyond the toe, and surface cracks which indicate movement.

c. Seepage. The downstream face of abutments, embankment slopes and toes, embankment - structure contacts, and the downstream valley areas should be examined for evidence of existing or past seepage. The sources of seepage should be investigated to determine cause and potential severity to dam safety under all operating conditions. The presence of animal burrows and tree growth on slopes which might cause detrimental seepage should be examined.

d. Drainage Systems. All drainage systems should be examined to determine whether the systems can freely pass discharge and that the discharge water is not carrying embankment or foundation material. Systems used to monitor drainage should be examined to assure they are operational and functioning properly.

e. Slope Protection. The slope protection should be examined for erosion-formed gullies and wave-formed notches and benches that have reduced the embankment cross-section or exposed less wave resistant materials. The adequacy of slope protection against waves, currents, and surface runoff that may occur at the site should be evaluated. The condition of vegetative cover should be evaluated where pertinent.

3. Spillway Structures. Examination should be made of the structures and features including bulkheads, flashboards, and fuse plugs of all service and auxiliary spillways which serve as principal or emergency spillways for any condition which may impose operational constraints on the functioning of the spillway.

a. Control Gates and Operating Machinery. The structural members, connections, hoists, cables and operating machinery and the adequacy of normal and emergency power supplies should be examined and tested to determine the structural integrity and verify the operational adequacy of the equipment. Where cranes are intended to be used for handling gates and bulkheads, the availability, capacity and condition of the cranes and lifting beams should be investigated. Operation of control

Figure A2. (Continued)

systems and protective and alarm devices such as limit switches, sump high water alarms and drainage pumps should be investigated.

b. Unlined Saddle Spillways. Unlined saddle spillways should be examined for evidence of erosion and any conditions which may impose constraints on the functioning of the spillway. The ability of the spillway to resist erosion due to operation and the potential hazard to the safety of the dam from such operation should be determined.

c. Approach and Outlet Channels. The approach and outlet channels should be examined for any conditions which may impose constraints on the functioning of the spillway and present a potential hazard to the safety of the dam.

d. Stilling Basin (Energy Dissipators). Stilling basins including baffles, flip buckets or other energy dissipators should be examined for any conditions which may pose constraints on the ability of the stilling basin to prevent downstream scour or erosion which may create or present a potential hazard to the safety of the dam. The existing condition of the channel downstream of the stilling basin should be determined.

4. Outlet Works. The outlet works examination should include all structures and features designed to release reservoir water below the spillway crest through or around the dam.

a. Intake Structure. The structure and all features should be examined for any conditions which may impose operational constraints on the outlet works. Entrances to intake structure should be examined for conditions such as silt or debris accumulation which may reduce the discharge capabilities of the outlet works.

b. Operating and Emergency Control Gates. The structural members, connections, guides, hoists, cables and operating machinery including the adequacy of normal and emergency power supplies should be examined and tested to determine the structural integrity and verify the operational adequacy of the operating and emergency gates, valves, bulkheads, and other equipment.

c. Conduits, Sluices, Water Passages, Etc. The interior surfaces of conduits should be examined for erosion, corrosion, cavitation, cracks, joint separation and leakage at cracks or joints.

d. Stilling Basin (Energy Dissipator). The stilling basin or other energy dissipator should be examined for conditions which may impose any constraints on the ability of the stilling basin to prevent downstream scour or erosion which may create or present a potential hazard to the safety of the dam. The existing condition of the channel downstream of the stilling basin should be determined by soundings.

Figure A2. (Continued)

e. Approach and Outlet Channels. The approach and outlet channels should be examined for any conditions which may impose constraints on the functioning of the discharge facilities of the outlet works, or present a hazard to the safety of the dam.

f. Drawdown Facilities. Facilities provided for drawdown of the reservoir to avert impending failure of the dam or to facilitate repairs in the event of stability or foundation problems should be examined for any conditions which may impose constraints on their functioning as planned.

5. Safety and Performance Instrumentation. Instruments which have been installed to measure behavior of the structures should be examined for proper functioning. The available records and readings of installed instruments should be reviewed to detect any unusual performance of the instruments or evidence of unusual performance or distress of the structure. The adequacy of the installed instrumentation to measure the performance and safety of the dam should be determined.

a. Headwater and Tailwater Gages. The existing records of the headwater and tailwater gages should be examined to determine the relationship between other instrumentation measurements such as stream flow, uplift pressures, alignment, and drainage system discharge with the upper and lower water surface elevations.

b. Horizontal and Vertical Alignment Instrumentation (Concrete Structures). The existing records of alignment and elevation surveys and measurements from inclinometers, inverted plumb bobs, gage points across cracks and joints, or other devices should be examined to determine any change from the original position of the structures.

c. Horizontal and Vertical Movement, Consolidation, and Pore-Water Pressure Instrumentation (Embankment Structures). The existing records

of measurements from settlement plates or gages, surface reference marks, slope indicators and other devices should be examined to determine the movement history of the embankment. Existing piezometer measurements should be examined to determine if the pore-water pressures in the embankment and foundation would under given conditions impair the safety of the dam.

d. Uplift Instrumentation. The existing records of uplift measurements should be examined to determine if the uplift pressures for the maximum pool would impair the safety of the dam.

e. Drainage System Instrumentation. The existing records of measurements of the drainage system flow should be examined to establish the normal relationship between pool elevations and discharge quantities and any changes that have occurred in this relationship during the history of the project.

Figure A2. (Continued)

f. Seismic Instrumentation. The existing records of seismic instrumentation should be examined to determine the seismic activity in the area and the response of the structures to past earthquakes.

6. Reservoir. The following features of the reservoir should be examined to determine to what extent the water impounded by the dam would constitute a danger to the safety of the dam or a hazard to human life or property.

a. Shore line. The land forms around the reservoir should be examined for indications of major active or inactive landslide areas and to determine susceptibility of bedrock stratigraphy to massive landslides of sufficient magnitude to significantly reduce reservoir capacity or create waves that might overtop the dam.

b. Sedimentation. The reservoir and drainage area should be examined for excessive sedimentation or recent developments in the drainage basin which could cause a sudden increase in sediment load thereby reducing the reservoir capacity with attendant increase in maximum outflow and maximum pool elevation.

c. Potential Upstream Hazard Areas. The reservoir area should be examined for features subject to potential backwater flooding resulting in loss of human life or property at reservoir levels up to the maximum water storage capacity including any surcharge storage.

d. Watershed Runoff Potential. The drainage basin should be examined for any extensive alterations to the surface of the drainage basin such as changed agriculture practices, timber clearing, railroad or highway construction or real estate developments that might extensively affect the runoff characteristics. Upstream projects that could have impact on the safety of the dam should be identified.

7. Downstream Channel. The channel immediately downstream of the dam should be examined for conditions which might impose any constraints on the operation of the dam or present any hazards to the safety of the dam. Development of the potential flooded area downstream of the dam should be assessed for compatibility with the hazard classification.

8. Operation and Maintenance Features.

a. Reservoir Regulation Plan. The actual practices in regulating the reservoir and discharges under normal and emergency conditions should be examined to determine if they comply with the designed reservoir regulation plan and to assure that they do not constitute a danger to the safety of the dam or to human life or property.

b. Maintenance. The maintenance of the operating facilities and features that pertain to the safety of the dam should be examined to determine the adequacy and quality of the maintenance procedures followed in maintaining the dam and facilities in safe operating condition.

Figure A2. (Continued)

Concrete Dam

Upstream face	_____
Downstream face	_____
Crest	
Roadway	_____
Walks	_____
Parapet wall	_____
Lighting, etc.	_____
Galleries	
Concrete	_____
Metalwork	_____
Electrical	_____
Ventilation	_____
Drains and drainage	_____
Elevator shaft	
Metalwork	_____
Equipment	_____
Safety inspection	_____
Abutments	_____
Foundation at downstream toe of dam	_____
Leakage around dam	
Location	_____
Amount	_____
Measurement methods	_____
Performance instruments and devices	
Uplift measurements	_____
Drain flow	_____

Figure A3. Concrete dams checklist (Bureau of Reclamation RO&M Program)

UPSTREAM FACE	_____
DOWNSTREAM FACE	_____
General condition	_____
Seepage	_____
CREST	
Offsets	_____
Roadway	_____
Walks	_____
Parapet wall	_____
Lighting, etc.	_____
GALLERIES	
Concrete	_____
Metalwork	_____
Electrical	_____
Ventilation	_____
Seepage	_____
Drains and drainage (all drains should be open)	_____
Frequency of cleaning or probing	_____
FOUNDATION TUNNELS	
General	_____
Seepage	_____
INSTRUMENTATION	
Structural	_____
Seepage	_____
ICE-PREVENTION SYSTEM	_____
OTHER	_____

ABUTMENTS

	<u>Left</u>	<u>Right</u>
FOUNDATION AT DOWNSTREAM TOE OF DAM	_____	_____
Leakage around dam	_____	_____
Location	_____	_____
Amount	_____	_____
Measurement methods	_____	_____
Joint patterns	_____	_____
OTHER	_____	_____
	_____	_____

Figure A4. Checklist for examination of concrete dams
(Bureau of Reclamation - SEED Program)

Hole in Wall - Complete deterioration of channel wall/side slope to backfill.

Low - less than 0.25 sq. ft. in area

Med. - between 0.25 sq. ft. and 0.50 sq. ft. in area

High - greater than 0.50 sq. ft. in area

Extent of Exposed Steel - Deterioration of channel wall/side slope to reinforcement steel.

Longitudinal steel

Transverse steel

Low - less than 5 ft. in length

Less than 2 bars/slab

Med. - 5 to 20 ft. in length

2-3 bars/slab

High - more than 20 ft. in length

More than 3 bars/slab

Condition of Exposed Steel - Deterioration of exposed reinforcement steel.

Low - any reinforcement steel exposed

Med. - reinforcement steel shows excessive corrosion

High - reinforcement steel completely, corroded through

Spalling - Deterioration of channel wall/side slope to, but not including, exposure of steel.

Low - less than 1 sq. ft. in area and less than 2 inches in depth

Med. - greater than 1 sq. ft. in area and less than 2 inches in depth

High - greater than 2 inches in depth

Cracking in Wall - Horizontal and diagonal cracks.

Low - less than 0.02 inch in width and less than 24 inches in length

Med. - less than 0.02 inch in width and greater than 24 inches in length or between 0.02 inch and 0.10 inch in width

High - greater than 0.10 inch in width

Figure A5. Channel wall or wide slope distress
(Los Angeles Flood Control District)

Joint Seal Damage - Ground water seepage through channel wall/side slope joints.

Low - evidence of previous seepage (small amounts of debris around joint cracks)

Med. - water and/or backfill material trickling through joints

High - water and/or backfill material running through joints

Joint Faulting - Movement of channel wall/side slope detected at construction joints.

Low - less than 0.50 inch differential between channel walls/side slopes

Med. - between 0.50 inch and 1 inch differential between channel walls/side slopes

High - more than 1 inch differential between channel walls/side slopes

Weep Holes/Rodent Activity - At channel wall/side slope weep holes, two problems can be detected: 1) plugging of weep holes so that ground water could build up behind the channel walls/side slopes; 2) tunneling through weep holes by rodents so that there may be voids in the backfill supporting the channel wall/side slope.

Low - less than 10 percent plugged or
minor debris deposition on invert slab immediately below weep hole

Med - between 10 & 25 percent plugged or
medium debris deposition on invert slab

High - greater than 25 percent plugged or
large debris deposition on invert slab

Separation at Side Inlets

Low & Med. - no apparent separation at inlet connections to channel wall/side slope nor differential separation within side inlet

High - any apparent separation at inlet connections or
differential separation within side inlet

Void behind Channel Wall/Side Slope - Inspection made from atop channel to detect voids behind channel wall/side slope, settlement in parallel and abutting access road, or settlement of side slope.

Low - less than 2 cubic feet of void or settlement

Med. - between 2 and 5 cubic feet of void or settlement

High - greater than 5 cubic feet of void or settlement

Figure A5. (Continued)

10/04/83

CHANNEL INSPECTION SHEET

O&M Area WESTTG Page 18-25Date 10-09-83Facility Name: VERDUGO WASH*Section Limits: OPRECHEE WAY (STA 216+44) TO KILBASSO WAY (STA 228+00) Section No. 2Type of Channel: Rectangular ☒ TrapezoidalSoft Bottom Trapezoidal Channel: Yes ☐ No ☒

Flow Condition at: None

Low Flow: Defined Low-Flow Channel ☒ Undefined

Time of Inspection

Minor in Low Flow ☒Major in Low Flow ☐Inspected by: ROY P. HUGHES

Invert

Right Channel

Left Channel

Walked by: RDH

Top Walked by:

Top Walked by:

CHANNEL INVERT DISTRESS TYPES

Dist. No.	Distress	No	Yes	Severity			Comments (Circle Appropriate Comments as Provided or Provide Comments)
				Low	Med	High	
1A	Hole in Invert	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Within Confined Low-Flow: Yes <input type="checkbox"/> No <input type="checkbox"/>
2A	Extent of Exposed Steel	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Adjacent to: Channel Wall <input checked="" type="checkbox"/> Center Line <input type="checkbox"/> Midway Bwn Channel Wall & Center Line <input type="checkbox"/>
3A	Condition of Exposed Steel	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
4A	Spalling & Pitting	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
5A	Scour in Low-Flow	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<u>ENTIRE LENGTH OF LOW FLOW</u>
6A	Cracking Longitudinal	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Adjacent to: Channel Wall <input type="checkbox"/> Center Line <input type="checkbox"/> Midway Bwn Channel Wall & Center Line <input type="checkbox"/>
7A	Cracking Transverse	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Adjacent to: Channel Wall <input type="checkbox"/> Center Line <input type="checkbox"/> Midway Bwn Channel Wall & Center Line <input type="checkbox"/>
8A	Ground Water Seepage	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Through Joints <input type="checkbox"/> Cracks <input type="checkbox"/>
9A	Joint Faulting	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<u>EVERY JOINT COATED WITH TAR - IN GOOD CONDITION</u>
10A	Bulging	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

CHANNEL WALL OR SIDE SLOPE DISTRESS TYPES

Dist. No.	Distress	No	Yes	Severity	Comments	Left Wall	Right Wall
1B	Hole in Wall/Slope	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Notes: Top <input type="checkbox"/> Bottom <input type="checkbox"/>		
2B	Extent of Exposed Steel	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
3B	Condition of Exposed Steel	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
4B	Spalling of Wall/Slope	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<u>SOME SPALLING HAS BEEN PATCHED</u>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
5B	Cracking	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Horizontal <input type="checkbox"/> <u>Diagonal</u> <input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
6B	Joint Seal Damage	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			
7B	Joint Faulting	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			
8B	Weep Holes/ Rodent Act	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Weep Holes Plugged <input type="checkbox"/> Rodent Activity <input type="checkbox"/>		
9B	Separation at Side Inlets	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			
10B	Voids behind Wall/Slope	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Voids <input type="checkbox"/> Settlement: Access Road <input type="checkbox"/> Side Slope <input type="checkbox"/>		

*If a section of invert or channel top is not accessible for inspection, indicate the reason for lack of access and any apparent high distresses on a sketch.

**All Med Distress types must be documented on a sketch.

***All High Distress types must be photographed and documented on a sketch.

SECTION SKETCH




Figure A6. An example sheet of channel inspection
(Los Angeles Flood Control District)

FEATURE	CONDITION**		Remarks (Record any change from previous inspections or condition that should be corrected)
	S	U	
Spillway	Upstream Face ¹		
	Downstream Face ¹		
	Deck ^{1,2,3}		
	Piers and Training Walls ^{1,3}		
	Drainage Gallery ⁶		
North & South Embankments	Upstream Slope ⁴		
	Downstream Slope ⁴		
	Roadway ⁴		
	Abutments ⁵		

1. On concrete surfaces look for spalls, cracks, leaks, or movement at joints. Upstream face to be inspected from a boat semiannually at high and low reservoir.
2. On concrete decks, walls, floors, and ceilings check condition of drains, gutters, and joint filler.
3. Check paint and anchorage of handrailings, steel ladders, steel framing members, pipes, and grating.
4. On embankments check for subsidence of slopes, spalling or movement of riprap, erosion on slopes, settlement or cracks in roadway, and springs or wet areas on the downstream slope.
5. Check abutments for erosion adjacent to the dam and for springs or wet areas on the downstream side.
6. If galleries check for leaks and condition of drains and gutters, ladders, lighting, and sump as well as items noted in No. 1 above.
7. Check condition of riprap and training walls.

Figure A7. Inspection checklist for T/A

UPSTREAM FACE

	S*	U*	REMARKS
SURFACE CONDITION	x		
CRACKS / SPALLS	x		
JOINT MOVEMENT	x		
ADDITIONAL REMARKS:			

DOWNSTREAM FACE

	S	U	REMARKS
SURFACE CONDITION	x		
CRACKS / SPALLS	x		
JOINT MOVEMENT	x		
LEAKAGE	x		
ADDITIONAL REMARKS:			

ROADWAY

	S	U	REMARKS
SURFACE CONDITION	x		
CRACKS / SPALLS	x		
JOINT MOVEMENT	x		
ADDITIONAL REMARKS:			

Figure A7. (Continued)

DAM INSPECTION CHECKLIST						Date _____ Time _____	
NAME OF DAM _____ FILE NUMBER _____ COUNTY _____ CLASS _____ WEATHER & SITE CONDITIONS _____ INSPECTORS _____ OTHERS _____							
CHECK AREA AS INSPECTED	CONCRETE DAM TYPE _____					ACTION	
	CHECK/CIRCLE CONDITION NOTED	OBSERVATIONS	REPAIR	MONITOR	INVESTIGATE		
U/S FACE	deteriorated joints						
	cracking/spalling						
CREST	deteriorated joints						
	cracking/spalling						
	poor alignment						
D/S FACE	deteriorated joints						
	cracking/spalling						
	seepage						
ABUT- MENTS	vegetation/erosion						
	sloughs/slides/cracks						
	seepage/wetness						
TOE	erosion/undermining						
	seepage/wetness						
	foundation drains						
GAL- LERY	deteriorated joints						
	cracking/spalling						
	seepage						
GENERAL COMMENTS, SKETCHES & FIELD MEASUREMENTS							

Figure A3. Concrete dam inspection (Ohio Department of Natural Resources)

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SURFACES: Surface Cracks Spalling		
STRUCTURAL CRACKING		
ALIGNMENT: Vertical Horizontal		
MONOLITH JOINTS		
CONSTRUCTION JOINTS		
STAFF GAGE OR RECORDER		

Figure A9. Concrete/masonry dams (Pennsylvania Department of Environmental Resources)

Satisfactory-No Change Requires Work or Further Investigation	Date Corrected	Job Number	
			2. Patrol - review frequency and method
			3. Gates - spill and cross
			4. Recorders, float wells and gages
			5. Alarms - operability and settings
			6. Grizzlies and trash rakes
			7. Rodent control on berm
			8. Vegetation control, including hazard trees adjacent to canal
			9. Leakage or wet spots - on or below berm
			10. Deer crossings and escape ramps - damage
			11. Erosion and slides - banks or berms
			12. Flow obstructions and restrictions
			13. General housekeeping, debris disposal
			14. Diversions - authorized, unauthorized (SP 028.43-1)
			15. Indications of overtopping canal or flume
			16. Spillways
			a. Flashboards or gates
			b. Chutes secure from public entry
			c. Erosion
			d. Obstructions in channels - vegetation, debris
			e. Channel encroachments
			f. Remote controlled facilities
			g. Frequency of operation for rights (SP 483-1)

Figure A10. (Continued)

Satisfactory-No Change Requires Work or Further Investigation	Date Corrected	Job Number	
			17. Flumes
			a. Leakage
			b. Condition of sheets
			c. Substructure - condition
			d. Settlement
			e. Footings - erosion or ground movement, clearances around footings
			f. Walkways and handrails - employee and public safety
			g. Warning signs, public safety
			18. Siphons
			a. Foot patrol
			b. Air valves and vents (Bull. #30)
			*c. Leakage
			*d. Supports and anchors
			e. Expansion joints
			*f. Erosion and slides
			g. Protective coatings
			h. Drains
			19. Security-fencing and locks on valves, gates, etc.
			20. Wire and radio communications
			*21. Unauthorized activities in vicinity of canal - logging, roads, drilling, blasting, etc.
			22. Copper sulfate feeders
			23. Condition of trails

Figure A10. (Continued)

Indicator	Possible Causes	Possible Effects	Potential Remedial Measures (listed roughly in order of recommended action)	Indicator	Possible Causes	Possible Effects	Potential Remedial Measures (listed roughly in order of recommended action)
(A) Concrete (general) Cracking (shallow) Coating Spalling	Freeze thaw cycling Reactivity Sulfate attack Leaching Aging	Accelerated deterioration Reduction of allowable stresses Infiltration of chloride solution Increased stresses Loss of weight Increased leakage	Determine concrete qualities by testing Cutting Petographic Density Sonic (physical) Porosity and permeability Impact Modulus of elasticity Determine loss of section and weight Perform stress/stability analysis Protect local surfaces from exposure and water Coatings Grout Concrete Steel	(C) Concrete Deep cracking	Excessive loading Overstress Uplift Shrinkage (usually occurs early in life) Expansion Foundation movement Sediment activity Loss of strength Concrete creep	Increased leakage Accelerated deterioration Progressive cracking Stress redistribution Increased stresses Reduced stability Differential movement	Determine depth/extent of cracking Sonic testing Coreing Interior inspection, from gully or if possible Seal or grout cracks Evaluate short- and long-term effects Assess effects on stresses and stress redistribution Assess potential for leakage and consequent results Determine cause Check for movement Perform loading analysis Perform stress analysis Perform stability analysis Eliminate cause if feasible Increase drainage Seal upstream face
(B) Concrete (local) Spalling and cracking	Stress Freeze thaw action Differential movement	Porous surface deterioration Increase leakage Loss of section Stress Water intrusions	Conduct survey and establish monitoring system Install pins, monuments, or other devices to accurately measure opening and be kept in points Determine quality of deteriorated concrete similarly to (A) Remove and repair deteriorated sections with coatings or cover	(D) Leakage Moist or wet surface in concrete	Cracks Deteriorated concrete Porous concrete	Increased rate of deterioration Leaking Loss of weight Loss of strength Increased leakage	Review to determine if causes relating to (A) apply and pursue same remedial measures Determine depth and extent of cracks and water (C) for possible remedial measures Map location of all leaks Monitor quantities and relate to reservoir elevation and other potential inflow in existing conditions Determine path of water if possible
				(E) Leakage Concrete through concrete	Cracks Differential movement Open joints High uplift Leaking pipes and conduits Plugged drains	Loss of concrete matrix Loss of structural integrity Increased uplift	

Figure All. Evaluation matrix of masonry dams (Safety of Existing Dams)

Indicator	Possible Causes	Possible Effects	Potential Remedial Measures (listed roughly in order of recommended action)	Indicator	Possible Causes	Possible Effects	Potential Remedial Measures (listed roughly in order of recommended action)
(K) Impermeability of gates and valves	Poor design	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Block beds (blocks or badly rock)	(B) Debris	Flushing Logging Vegetation	Plugging of spillways Plugging of outlets Damage to trash racks and equipment	Review loading and dam stability and correct
	Poor foundation		Increase spillway capacity to prevent overtopping				Prestress load above
	Piping or leakage		Controlled spills and provide proper energy dissipation				Remove only silt close to dam (temporary measure)
(L) Reservoir slides	Poor drainage	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Inspect operating parts and replace or replace	(C) High waves	Wind Reservoir slides	Overtopping Damage to equipment Undermining of banks	Increase sloaking (will usually affect only area close to outlet)
	Normal weathering		If capacity on release water is inhibited, consider temporary change in reservoir operations				Regularly remove debris from reservoir
			Methodically and systematically determine cause				Provide log/debris boom
(M) Siltation	Failed gate or corrosion	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Provide erosion protection	(D) Ice	Cold weather	Accelerated deterioration Blockage of spillways and outlets Damage to piping and equipment Misoperation of gates Damage to trash racks Parapet damage Increased loading	Provide emergency spill to skim off high water
	Obstructions		If ice is problem, provide barriers or at least, see (B)				Provide sluicing gate or chute to dispose of material over the dam
	Blockages		If due to silt, debris, or other blockage, remove that cause				Simplify spillway arrangement so debris can be passed without plugging
(N) Reservoir slakes	Debris	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Provide log booms, debris barriers, trash racks or other facility to alleviate blockage	(E) High waves	Wind Reservoir slides	Overtopping Damage to equipment Undermining of banks	Increase freeboard to prevent overtopping
	Silt deposits		Provide erosion protection				Protect equipment against high water
	Ice		If ice is problem, provide barriers or at least, see (B)				Design parapet wall to deflect waves back to reservoir
(O) Reservoir slakes	Differential movements	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Determine potential for waves and damage to dam	(F) Ice	Cold weather	Accelerated deterioration Blockage of spillways and outlets Damage to piping and equipment Misoperation of gates Damage to trash racks Parapet damage Increased loading	Provide emergency spill to skim off high water
			Stabilize slide (see Chapter 7)				Operate reservoir to keep ice at level where damage will be minimal
			Modify reservoir operation				Keep spillways gates open
(P) Reservoir slakes	Unstable geology	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Divide reservoir (usually economic only for small reservoirs)	(G) High waves	Wind Reservoir slides	Overtopping Damage to equipment Undermining of banks	Simplify spillways so they can pass without restriction
	Saturation		Provide upstream siltation ponds				Provide aeration near operating equipment
	High runoff		Enlarge downstream spillways				Review loadings on dam resulting from ice and assure dam can tolerate
(Q) Reservoir slakes	Sloughing	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Provide erosion protection	(H) High waves	Wind Reservoir slides	Overtopping Damage to equipment Undermining of banks	Remove only silt close to dam (temporary measure)
			Stabilize slide (see Chapter 7)				Operate reservoir to keep ice at level where damage will be minimal
			Modify reservoir operation				Keep spillways gates open
(R) Siltation	Geology	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Divide reservoir (usually economic only for small reservoirs)	(I) High waves	Wind Reservoir slides	Overtopping Damage to equipment Undermining of banks	Simplify spillways so they can pass without restriction
	Normal or abnormal inflow		Provide upstream siltation ponds				Provide aeration near operating equipment
	Calculation		Enlarge downstream spillways				Review loadings on dam resulting from ice and assure dam can tolerate
(S) Reservoir slakes	upstream	Inability to operate Reduced capacity of spillways/blocks Increased possibility of overtopping	Provide erosion protection	(J) High waves	Wind Reservoir slides	Overtopping Damage to equipment Undermining of banks	Remove only silt close to dam (temporary measure)
	Vegetation removal		Stabilize slide (see Chapter 7)				Operate reservoir to keep ice at level where damage will be minimal
			Modify reservoir operation				Keep spillways gates open

Figure All. (Continued)

Indicator	Possible Causes	Possible Effects	Potential Remedial Measures (listed roughly in order of recommended action)
(F) Leakage Through concrete (noticeable change)	Erosion or cavitation of concrete Leaching		<p>Potential Remedial Measures (listed roughly in order of recommended action)</p> <p>Detail inspection Dye tests Check condition of pipes, conduits, drains, etc. and repair if necessary. Assess short- and long term consequences. Alter or terminate sources, try to plug or seal the crack or opening at upstream side. Determine basic cause, e.g., movement, stress conditions, and correct</p>
(F) Leakage Through concrete (noticeable change)	Self sealing of cracks Plugged drains Broken drains Differential movement Concrete failure	Increased uplift Loss of concrete Stress redistribution	
(G) Leakage From foundation abutments	Foundation deterioration Inadequate drains Opening of joints, seams, etc., etc. Movement	Foundation weakening with potential failure Piping through foundation Increased uplift Loss of stability Differential movement of dam Loss of reservoir water Loss of support	<p>Map location of all leaks Observe vegetation or other signs of moisture Infrared film a possibility Pursue measures similar to (F) Spectrally assess hazards associated with leaks, piping, or seepage Seal source of leakage with impervious material Seal with sand cement, chemical grout, or other suitable Protect individual drainage system Add free draining stability material on downstream side</p>
(H) Movement	Foundation settlement or heave Abutment movement Sinkhole activity Overtopping Excessive loading or uplift Concrete expansion due to chemical action	Increased leakage opportunities Severe cracking Stress redistribution Reduction in stability Anomalous changes in section or plan	<p>Potential Remedial Measures (listed roughly in order of recommended action)</p> <p>Establish survey control system. Measurements for horizontal control - some must be sufficiently far from dam to be out of influence zone Monuments for vertical control. Pins, monuments, plates, gages, etc., across joints Inspect after each sink event. Establish photographic record Check for changes in leakage Isolate whether cause is in foundation/abutment or dam. Review loadings Analyze foundation or abutment similarly to embankment dam Remedial measures are highly dependent on results of above Same measures as for (H)</p>
(I) Displacement of objects	Foundation movement Differential movement Seismic activity Underlain by loose backwater channel capacity Channalization of water (quills or stream flow)	Increased cracking and spalling Increased leaks Blinding of gates and operators Block running face of tablets Complete failure of appurtenances	
(J) Friction and foundation at toe or at outlets and spillway	Foundation and abutment movement Channalization of water (quills or stream flow)	Block running face of tablets Complete failure of appurtenances	

Figure All. (Continued)

APPENDIX B: CHECKLISTS AND EXPLANATORY
MATERIALS FOR ROCK AND EARTH DAMS

PREVENTIVE MAINTENANCE SYSTEM

WATTS BAR LOCK		PERIOD ENDING 12/31/83		PAGE			
CITIZEN NO.	NOMENCLATURE	LOCATION	MODEL NUMBER	SERIAL NUMBER	FILE NUMBER	MANUFACTURE	SVC DTE
OF WORK BEG OF WORK END PROJ LHM NONPROJ LAR MTRL COST		WORK DESCRIPTION					
WHL 000A	FLOORS CONC & TRKZ	OPER BLDG & CS					/ /
01/15/80	04/15/80	40500	200500	REPEATED CONTROL SHELTERS			
11/25/81	11/26/81	31300	61200	POURED AND FINISHED HOLE IN TERMINAL FLOOR LEFT BY REMOVAL OF OLD SWITCHBOARD			
WHL 102A	VALVE	OPER BLDG & CS					/ /
11/11/80	10/02/80	10200	1100500	SANDBLASTED CAULKED AND PAINTED EXISTING WALLS OF OPERATIONS BLDG			
WHL 100A	MONOLITH JOINTS	LOCK TACE					/ /
01/07/80	04/27/80	67200	GROUTED MONOLITH JOINTS AT STATION 0-39 STA 3-2033R STA 3-5417R RIVER WALL AND STATION 3-2233R LANDWALL				
04/29/81	04/30/81	16301	64500	APPLIED PATCH BELOW WATER LINE AT LOWER RIVER WALL VALVE BULKHEAD SLOT			
07/19/82	07/22/82	32500	1534	POURED JOINTS WITH 15 UNITS OF NR 200 SEALANT AND 3 UNITS OF P200 PR			
WHL 102A	VALVE BULKHEAD RECC	LOCK WALLS					/ /
04/15/80	04/26/80	40500	REPAIRED CAVITATION ON EMBEDDED STEEL WITH BEZOLA MOLECULAR STEEL REPAIRED DETERIORATED CONCRETE WITH NORODAK WEARING COMPOUND				

Figure B1. Maintenance work history (Nashville District)

WATTS BAR LOCK

PAGE

CONTROL NUMBER	NOMENCLATURE	LOCATION	MODEL NUMBER	SERIAL NUMBER	FILE NUMBER
INSP. CO.	SERVICES REQUIRED		LAST INSP. DATE		
UWL 1009	GATE SILLS	LOCK CHAMBER			
	A7	CHECK FOR CRACKS, LEAKS, & DETERIORATION OF CONCRETE	03/84		
UWL 1012	PILE GAGES	LOCK WALLS EMBUD			
	RA	CLEAN AT INTERVALS REQUIRED TO FACILITATE READING	03/84		
	RI	CHECK FOR CRACKS, SEALLING OR ABRASION	03/84		
UWL 1015	TUNNELS & GALLERIES	LOCK WALLS			
	HC	CHECK FOR CRACKS, LEAKS, & CLOGGED DRAINS	03/84		
	HD	CHECK FOR VENTILATION & DETERIORATION OF CONCRETE	03/84		
UWL 1024	MACHINE RECES, BEAMS	LOCK WALLS			
	HG	INSPECT FOR RUST, DETERIORATION & RIGIDITY	03/84		
	HH	INSPECT FOR BROKEN WELDS & DEFECTIVE MEMBERS	05/83		
	HI	INSPECT FOR LOOSE BOLTS ON SUPPORTING ANCHORAGES	05/83		
UWL 1032	FRAMES & SUPPORTS	LOCK WALLS			
	HG	INSPECT FOR RUST, DETERIORATION & RIGIDITY	03/84		
	HH	INSPECT FOR BROKEN WELDS & DEFECTIVE MEMBERS	05/83		
	HI	INSPECT FOR LOOSE BOLTS ON SUPPORTING ANCHORAGES	05/83		
UWL 1034	GRATINGS & COVERS	LOCK WALLS			
	UG	INSPECT FOR RUST, DETERIORATION & RIGIDITY	03/84		
	UH	INSPECT FOR BROKEN WELDS & DEFECTIVE MEMBERS	05/83		
	UI	INSPECT FOR LOOSE BOLTS ON SUPPORTING ANCHORAGES	05/83		

Figure B1. (Continued)

WHL 048 LOCK		PAGE	
CONTROL NUMBER	NONFUNCTION	LOCATION	MODFL NUMBER
INSP. CD.	SERVICES REQUIRED	LAST INSP. DATE	FILE NUMBER
			02/11/00000000 0111
WHL 301 HOISTING ASSEMBLIES			
	LOCK VALVES		
	CT CHECK CONNECTING PINS, SPRINGS, & CONTROL SWITCHES	09/83	04/84
WHL 404 BRAKES GATE & VALVE			
	GA & VL OPER MAC		
	EH CHECK WEAR OF BRAKE LININGS & TENSION ON BRAKE SHOES	05/83	12/83
	EI REMOVE COVER, CLEAN & OIL ALL PIVOT POINTS	05/83	12/83
	FJ CHECK BRAKE DRUM FOR SCORES & WEAR	05/83	12/83
	EK CHECK WOT & KEY SECURING BRAKE DRUM OR WHEEL	05/83	12/83
	EL CHECK BRAKE BENDIX & MOTOR	05/83	12/83
	EH CHECK ELECTRICAL CIRCUITS & HEATING SYSTEM	05/83	12/83
	EN CHECK WEATHER PROOF GASKET OF COVER PLATE	05/83	12/83
WHL 406 LIMIT SWITCHES			
	GA & VL OPER MAC		
	EO REMOVE COVER	05/83	12/83
	EP CLEAN ALL CONTACTS OR REPLACE IF NECESSARY	05/83	12/83
	EQ CHECK ALL ELECTRICAL WIRING	05/83	12/83
	ER LUBRICATE THREADED ROD	05/83	12/83
	ES CHECK GASKETS & SEALS FOR MOISTURE PROOFING	05/83	12/83
	ET CHECK HEATERS	05/83	12/83
WHL 504 BARGE HAULAGE UNITS			
	MACHINERY RECESS		
	FC INSPECT FOR WEAR OF GEARS, BEARINGS, & BRAKES	11/83	03/84
	FD INSPECT FOR WEAR OF SHEAVES & CLUTCH LININGS	11/83	03/84
	FE INSPECT HAULAGE CABLE	11/83	03/84
	FG INSPECT MOTOR SLIP RINGS & CONTROLLER CONTACTOR FINGERS	11/83	03/84
WHL 604 LIFE VESTS			
	ENR FAC & EQUIP		
	GG IF 11 EACH LIFE VEST FOR HUOYANCY	08/83	03/84

Figure B1. (Continued)

CTRL NO.	NOTIFICATION	LOCATION	HOURL NUMBER	SERIAL NUMBER	FILE NUMBER	MANUFACTURE	SVC C
INSP. CD.	SERVICES REQUIRED			LAST INSP DTE	NXT INSP DTE	INSP FR=0	LA00R(HR/MIN)
URL 0001	NAVIGATION LOC	TENN RIVER					
22	NON-SCHEDULE						3:30
URL 9004	FLOORS CONC & TRAY	OPER BLDG & CS					
AA	EXAMINE FOR CRACKS, SETTLEMENT, & SCALING		1/84		1/85	12	2:10
AB	EXAMINE FOR DUSTING, PITTING, & DETERIORATION		1/84		1/85	12	2:45
URL 0912	Ceilings	OPER BLDG & CS					
AF	CHECK FOR CRACKS IN PLASTER & DETERIORATED PLASTER		1/84		1/85	12	1:15
AF	CHECK FOR WATER STAINS & BROKEN OR DAMAGED ACoust TILE		1/84		1/85	12	1:50
AG	CHECK CONDITION OF PAINT		1/84		1/85	12	1:35
URL 0914	ROOFS & FLASHINGS	OPER BLDG & CS					
AM	INSPECT TO DETECT LEAKS & GULSTERS		4/83		4/85	12	7:10
URL 0020	WALLS	OPER BLDG & CS					
AK	CHECK FOR CRACKS IN PLASTER & WATER STAINS		1/84		1/85	12	1:40
AN	CHECK FOR MILDEN, DISFIGURATION, & OTHER DAMAGE		1/84		1/85	12	1:40
AO	CHECK FOR LOOSE MORTAR, BRICKS, & BLOCKS		1/84		1/85	12	1:55
AO	EXAMINE EXPANSION JOINTS, SEALER, & WEATHER STRIPPING		1/84		1/85	12	1:40
AR	EXAMINE CAULKING AROUND FRAMING, STOPS, & DOOR CLOSERS		1/84		1/85	12	2:25
AS	EXAMINE LOCKS, LATCHES, SCREENS, GLAZING, & HINGES		1/84		1/85	12	1:40
AC	CHECK FOR CORN, DIRTY OR LOOSE WALL PAPER		1/84		1/85	12	
URL 0923	WINDSHIELD & FOUNDATION	OPER BLDG & CS					

Figure B1. (Continued)

Upstream face

Riprap

Erosion - Beaching

Vegetative growth

Settlement

Debris

Downstream face

Rock

Vegetative growth

Crest

Roadway

Guardrails

Curb

Parapet wall

Settlement

Lighting

Abutments

Seepage and drainage

Location

Toe drain

Measurement

Method

Amount

Change in flow

Records

Performance instruments

Surface settlement points

Piezometer well

Readings

Figure B2. Checklist for earth dam (Bureau of Reclamation)

<u>DAM</u>		SEEPAGE AND DRAINAGE SUMMATION	
UPSTREAM FACE		Location(s)	_____
Slope protection	_____	Estimated flow(s)	_____
Erosion-beaching	_____	Color (staining)	_____
Vegetative growth	_____	Erosion of outfall	_____
Settlement	_____	Toe drain and relief wells	_____
Debris	_____	MEASUREMENT	
Burrows or burrowing animals	_____	Method	_____
Unusual conditions	_____	Amount	_____
		Change in flow	_____
		Clearness of flow	_____
DOWNSTREAM FACE		Color	_____
Signs of movement	_____	Fines	_____
Seepage or wet areas	_____	Condition of measurement devices	_____
Vegetative growth	_____	Records	_____
Channelization	_____	OTHER	_____
Condition of slope protection	_____		_____
Burrows or burrowing animals	_____		_____
Unusual conditions	_____	PERFORMANCE INSTRUMENTS	
ABUTMENTS		Piezometer well	
Seepage	_____	Well	_____
Cracks, joints, and bedding planes	_____	Frostfloor	_____
Channelization	_____	Ventilation	_____
Slides	_____	Gages	_____
Vegetation	_____	Piping	_____
Signs of movement	_____	Security	_____
CREST		Surface settlement points	_____
Surface cracking	_____	Crossarm devices	_____
Durability	_____	(deviation, station, and offset)	_____
Settlement	_____	Reservoir-level gage	_____
Lateral movement (alignment)	_____	Ice-prevention system	_____
Camber	_____	Other	_____

Figure B3. Checklist for examination of embankment dam
(Bureau of Reclamation - SEED Program)

SAN LUIS DAM
INSPECTION REPORT
DATE _____

By _____

Lake Elevation _____

Legend

X-No Change

O-Change

Item	Condition			Detailed Inspection	Photo No.	Remarks
	Requires Improvement	Sub. Std.	Std.			
<u>Crest</u>						
<u>Embankment</u>						
<u>Downstream</u>						
<u>Upstream</u>						
<u>Groins</u>						
<u>Upstream</u>						
<u>Right</u>						
<u>Left</u>						
<u>Downstream</u>						
<u>Right</u>						
<u>Left</u>						
<u>Saddle Valve</u>						
<u>Crest</u>						
<u>Embankment</u>						
<u>Downstream</u>						
<u>Upstream</u>						
<u>Groins</u>						
<u>Upstream</u>						
<u>Right</u>						
<u>Left</u>						

Figure B4. California aqueduct project surveillance

DAM INSPECTION CHECKLIST				Date _____ Time _____		
NAME OF DAM _____						
FILE NUMBER _____ COUNTY _____ CLASS _____						
WEATHER & SITE CONDITIONS _____						
INSPECTORS _____						
OTHERS _____						
CHECK AREA AS INSPECTED	EMBANKMENT • DIKE • LEVEE				ACTION	
	CHECK/CIRCLE CONDITION NOTED	OBSERVATIONS			REPAIR	MONITOR
U/S SLOPE	vegetation/norad					
	beaching/slides/cracks					
	undermining/erosion					
CREST	rut/erosion					
	cracks/settlement					
	poor alignment					
D/S SLOPE	vegetation/erosion					
	rodent burrows					
	sloughs/slides/cracks					
	seepage/wetness					
GROINS	vegetation/norad					
	erosion					
	seepage/wetness					
ABUT- MENTS	vegetation/erosion					
	sloughs/slides/cracks					
	seepage/wetness					
TOE	cracks/slump					
	embankment drains					
	seepage/wetness					
GENERAL COMMENTS, SKETCHES & FIELD MEASUREMENTS						

Figure B5. Ohio Department of Natural Resources
dam inspection checklist

DAM INSPECTION CHECKLIST				Date _____
NAME OF DAM _____				
FILE NUMBER _____ INSPECTORS _____				
<input type="checkbox"/> CHECK AREA AS INSPECTED	MISCELLANEOUS AREAS			ACTION
	CHECK/CIRCLE CONDITION NOTED	OBSERVATIONS	REPAIR	MONITOR INVESTIGATE
<input type="checkbox"/> MONITORING	piezometers			
	weirs			
	monuments			
<input type="checkbox"/> GAGES	rainfall			
	pool level			
	stream			
<input type="checkbox"/> POOL AND SHORELINE	erosion/ground cover			
	development			
	reservoir crossings			
	sedimentation			
	water quality			
<input type="checkbox"/> WATER-SHED	skoots			
	land use			
	other impediments			
<input type="checkbox"/> D/S AREA	stream channel			
	channel crossings			
	flood plain			
	development			
<input type="checkbox"/> EMERG. PLAN	notification list			
	evacuation plan			
	materials/equipment			
	access roads to dam			
GENERAL COMMENTS, SKETCHES & FIELD MEASUREMENTS				

Figure B5. (Continued)

Yes No	Remarks	Maintenance Tip
<input type="checkbox"/> <input type="checkbox"/> Are there any surface cracks?	May indicate movement within the dam.	Should be evaluated by a professional engineer.
<input type="checkbox"/> <input type="checkbox"/> Is there any unusual movement or cracking at or beyond the toe?	Dam or its foundation may be unstable.	Should be evaluated by a professional engineer.
<input type="checkbox"/> <input type="checkbox"/> Is there erosion on upstream face from wave action or changes in pool level?	If severe or rapid, a serious problem.	If severe and progressive, protect upstream face with rip-rap or other form of wave protection.
<input type="checkbox"/> <input type="checkbox"/> Is there erosion from runoff, either gullies or bare areas?	Erosion of any sort is a problem, as it tends to get worse with time if not corrected.	Improve grass cover; reshape embankment to improve drainage pattern.
<input type="checkbox"/> <input type="checkbox"/> Is there erosion from traffic (people, animals, vehicles)?	Any erosion is serious, as it will get worse with time if not corrected.	Try to keep all types of traffic to a reasonable level. Keep vehicles off dam. Stabilize crest roads to prevent rutting. Prohibit recreational vehicle traffic on slopes. Keep livestock off dam. Fill in existing ruts or eroded areas and reseed.
<input type="checkbox"/> <input type="checkbox"/> Are there any animal burrows?	May provide passageways for water into or through the dam.	Fill burrows with earth or otherwise block entry. Try to keep woodchucks, muskrat and beaver away from the dam.
<input type="checkbox"/> <input type="checkbox"/> Are there depressed areas on the dam?	May have resulted from slope failures or settlement, or even piping.	If pronounced or progressive, should be evaluated by a professional engineer.
<input type="checkbox"/> <input type="checkbox"/> Is there any evidence of piping? (This condition is evidenced by a muddy flow through the dam and/or the formation of soil deposits beyond the dam and depressions on its slopes.)	Piping is internal erosion within an embankment, or the progressive removal of soil particles adjacent to leaks through a soil mass.	Piping is always a serious condition, which can lead to failure of the dam. A piping condition should be evaluated by a professional engineer.
<input type="checkbox"/> <input type="checkbox"/> Does the crest appear to have shifted or settled excessively? (Look for cracks in the embankment and associated structures. Compare alignment with plans if they are available.)	Crest movement may indicate a stability problem. However, some settlement of a new fill, such as an embankment dam, is normal.	Should be evaluated by a professional engineer.

Figure B6. The embankment (Virginia Bureau of Water Control Management)

Yes	No	Remarks	Maintenance Tip	
<input type="checkbox"/>	<input type="checkbox"/>	If the upstream face is protected by riprap is it in good condition? (Riprap is a layer, facing, or protective mound of stone in random size pieces, randomly placed to prevent erosion, scour, or sloughing of an embankment or structure.)	Effectiveness is lessened if riprap has slipped out of place, has been undermined, or has become overgrown with brush.	Restore riprap as necessary; keep free of trees and bushes.
<input type="checkbox"/>	<input type="checkbox"/>	If there is riprap in discharge channels or in the plunge pool downstream, is it in good condition?	Has riprap stone been displaced or overgrown?	Restore riprap as necessary; keep free of trees and bushes.
<input type="checkbox"/>	<input type="checkbox"/>	If drainage channels at ends of embankment are protected with riprap, is it in good condition?	Drainage along abutments often causes gullying if there is no protection.	Riprap or other form of slope protection should be restored as necessary.
<input type="checkbox"/>	<input type="checkbox"/>	If there is riprap in miscellaneous areas (on downstream slope, on crest, etc.) is it in good repair?		Restore as necessary.
<input type="checkbox"/>	<input type="checkbox"/>	If there are any drains to collect and remove seepage, are they operating properly?	Check plans for the presence of drains, or search the dam to see if any are present.	Keep drains clear of any blockages and operating properly.
<input type="checkbox"/>	<input type="checkbox"/>	If there are foundation drain outlets, are they clear and flowing?	Foundation drains serve to collect seepage passing through the dam and conduct it away from the embankment.	Open outlets to such drains if they have become covered or damaged.
<input type="checkbox"/>	<input type="checkbox"/>	Are there wet spots or areas on the downstream face, at the toe, or beyond the dam? (Such spots are often indicated by a change in color or type of vegetation, such as from grass to cattails.)	<i>Some seepage is normal for an earth dam. Be concerned if it appears to be excessive (a lot of standing water; very soft and marshy areas; evidence of a seepage line high on the downstream face).</i>	<i>Observe seepage areas periodically to detect changes in the amount of moisture, new flows, or muddy flows. If the upper limit of seepage is fairly high on the downstream face, the dam may be unstable.</i>
<input type="checkbox"/>	<input type="checkbox"/>	Are there seeps or springs with flowing water? Look closely for these at the ends of the dam, around any pipes passing through the embankment, on downstream face, at the toe of the dam and beyond, and at the base of trees on, near, or below the dam.	Flowing seeps or springs may indicate problems, and should be observed periodically for changes in rate of flow or muddy flow. Creation of an impoundment often causes changes in the water table nearby.	Monitor seepage closely for any changes in amount, rate, extent, or clarity. Excessive or turbid seepage, or marked increases in rate of seepage, should be evaluated by a professional engineer.
<input type="checkbox"/>	<input type="checkbox"/>	Is there swamp or marsh type vegetation on downstream face or beyond the dam (cattails, tall grass, etc.)?	Swamp type vegetation indicates the presence of seepage.	Cut frequently to make observation of the area easier. Such growth can hide problems.

Figure B6. (Continued)

Earth Dams

Upstream Face

- ☐ Freeboard
- ☐ Wave Action
- ☐ Slope Protection
- ☐ Animal Burrows

Crest

- ☐ Erosion
- ☐ Slumps
- ☐ Cracks
- ☐ Movement

Downstream Slopes

- ☐ Abutments
- ☐ Slope Instability (slumps)
- ☐ Settlement
- ☐ Slope Protection
- ☐ Leakage
- ☐ Seepage - Embankment, toe, and downstream valley
- ☐ Erosion

Spillway Structure

- ☐ Primary Outlet - Inlet, and Trash Rack
- ☐ EMS - Approach channel, outlet channel, control section, and erosion
- ☐ Stilling Basin - Scour and Erosion
- ☐ Reservoir Drain - Operational?

Concrete Dams

- ☐ Face & Top - Surface Condition
- ☐ Cracking
- ☐ Deterioration
- ☐ Tilting - Movement
- ☐ Joints
- ☐ Abutments
- ☐ Leakage
- ☐ Seepage
- ☐ Foundation

Outlet Works

- ☐ Spillway-Type and Condition
- ☐ Gates - Method of Operation
- ☐ Stilling Basin
- ☐ Energy Dissipator

Figure B7. North Carolina Department of Natural Resources
dam inspection checklist

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS		
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE		
SLOUGHING OR EROSION: Embankment Slopes Abutment Slopes		
CREST ALIGNMENT: Vertical Horizontal		
RIPPRAP FAILURES		

Figure B8. Embankment inspection (Pennsylvania Department of Environmental Resources)


ITEMS TO ADDRESS		AREAS OF DAM
PROTECTION UNIFORMITY DISPLACEMENTS CRACKING EROSION	RODENT ACTIVITY OBSCURING GROWTH WETNESS CHANGES IN CONDITION	UPSTREAM FACE CREST DOWNSTREAM FACE
LOCATION CHARACTERISTICS OF AREA (i.e. SOFT, BOGGY, FIRM) QUANTITY TRANSPORTED OR DEPOSITED MATERIAL EFFLUENT QUANTITY AND COLOR	EXTENT OF AREA CONCENTRATED FLOWS BOILS COLOR TOE DRAIN	SEEPAGE
DETERIORATION ACCESSIBILITY CONDUIT LEAKAGE AROUND CONDUIT	OPERABILITY CONDITION GATE LEAKAGE UNDERCUTTING	OUTLET
DETERIORATION CONDITION OF CONTROL SECTION CHANNEL PROTECTION	CHANNEL OBSTRUCTION EROSION OR BACK CUTTING IN CHANNEL	SPILLWAY

Figure B9. Dam inspection report form checklist
(Colorado Division of Water Resources)

PROBLEM

5.4-1

EXCESSIVE MUDDY WATER EXITING FROM A POINT SOURCE



CAUSES & HARM DONE

Cause:

1. Water has created an open pathway, channel, or pipe through the dam. The water is eroding and carrying embankment material.
2. Large amounts of water have accumulated in the downstream slope. Water and embankment materials are exiting at one point. Surface agitation may be causing the muddy water.

Harm:

Continued flows can further erode embankment materials. This can lead to failure of the dam.

ACTION REQUIRED


Action:

1. Begin measuring outflow quantity and establishing whether water is getting muddier, staying the same, or clearing up.
2. If quantity of flow is increasing, the water level in the reservoir should be lowered until the flow stabilizes or stops.
3. A qualified engineer should inspect the condition and recommend further actions to be taken.

ENGINEER REQUIRED

5.4-2

EXCESSIVE AMOUNT OF WATER EXITING FROM A POINT SOURCE



Cause:

Water has created an open pathway or pipe through the dam.

Harm:

Continued flows can further erode embankment materials. This can lead to failure of the dam.


Action:

1. Begin measuring outflow quantity.
2. If quantity of flow is increasing, the water level in the reservoir may need to be lowered until the flow stabilizes or stops.
3. A qualified engineer should inspect the condition and recommend further actions to be taken.

ENGINEER REQUIRED

5.4-3

WATER EXITING FROM A POINT SOURCE HIGH ON THE EMBANKMENT



Cause:

1. Rodents, frost action, or poor construction have allowed water to create an open pathway or pipe through the embankment.

Harm:

1. Continued flows can saturate portions of the embankment and lead to slides in the area.
2. Continued flows can further erode embankment materials and lead to failure of the dam.

Action:

1. Begin measuring outflow quantity.
2. If quantity of flow is increasing, the water level in the reservoir needs to be lowered until the leak stops.
3. Search for opening on upstream side and plug it if possible.
4. A qualified engineer should immediately inspect the condition and recommend further action to be taken.

ENGINEER REQUIRED

Figure B9. (Continued) Dam inspection report form checklist (Colorado Division of Water Resources)

EARTH EMBANKMENTS

1. Dimensions/Shape _____

2. Foundation _____

3. Slopes _____

4. Crest _____

5. Seepage _____

6. Embankment/Abutment Junction _____

7. Drains _____

8. Staff Gage & Recorder _____

9. Other _____

Figure B10. Earth embankments (Kansas Division
of Water Resources)

Vegetation on dike and within 50 feet beyond toe of dike

a. Overgrowth

- (1) Requiring cutting for dike surveillance
- (2) Requiring weed control for dike surveillance
- (3) Indicating seepage or excessive capillarity

b. Wet Terrain Vegetation

- (1) Watch for boils
- (2) Watch for sand cones, deltas, etc.
- (3) Changes with the season, pond level changes

c. Incomplete: Requiring Repair

- (1) Poor growth
- (2) Destroyed by erosion

Drainage Ditches

a. Clogged with vegetation

a. Damp

c. Flowing water: Quantity

d. Boils

a. Silt accumulations, deltas, cones

Embankment

a. Freeboard - pond level

b. Crest

- (1) Cracking
- (2) Subsidence

c. Upstream Face

- (1) Cracking
- (2) Surface erosion, gullying
- (3) Wave erosion

d. Downstream Face

- (1) Cracking
- (2) Subsidence
- (3) Bulging
- (4) Erosion, gullies
 - (a) Depth
 - (b) Moisture on dry days
- (5) Damp areas
- (6) Boils, seeps

e. Berm and within 50 feet beyond toe of dike

- (1) Erosion, gullies
- (2) Damp areas
- (3) Boils, seeps

Spillways

a. Intake level, boards

b. Intake structure

c. Discharge conduit condition

d. Seepage or damp areas around conduit

e. Erosion below conduit

f. Boils in vicinity of conduit

g. Spillway slabs for uplift, subsidence, crack

Areas of previous repair

a. Effectiveness of repair

b. Progression of trouble into new area

Figure B11. Checklist of conditions to be noted
in safety inspections of small earth dams
(Safety of Existing Dams)

Defect	Possible Indicators	Possible Causes	Effects	Potential Remedial Measures
(A) Embankment mass movement (slope failure)	<p>Slumps on embankment face</p> <p>Longitudinal cracks</p> <p>Arcuate cracks</p> <p>Honeycombed (irregular) slope</p> <p>Bulge in slope</p> <p>Sag in crest</p> <p>Bent tree trunks</p> <p>Misaligned guard rails or similar structures</p>	<p>Inadequate strength</p> <p>Slopes too steep</p> <p>Phreatic surface too high</p> <p>Cracking due to differential settlement</p> <p>Earthquake</p> <p>Rapid drawdown of reservoir or tailwater</p> <p>Large trees on dam overturned</p> <p>Spillway or surface drainage discharge eroding embankment</p> <p>Temporary saturation due to rain storms, snowmelt, or high tailwater</p> <p>Decaying organic material in embankment</p>	<p>Possible massive failure of dam</p> <p>Damage to spillway or outlet works, resulting in dam failure</p>	<p>Determine specific cause(s) by test borings, strength tests, and piezometers. Based on test results, design appropriate remedies. Some alternatives are:</p> <p><i>Free-drawdown downstream buttress</i></p> <p>Flatten slopes</p> <p>Lower the phreatic surface upstream barrier, internal slurry wall or membrane cutoff, grouting</p> <p>Remove and replace weak soils</p> <p>Control surface erosion with riprap or other means</p> <p>Realign-relocate appurtenant structures as required</p> <p>Permanent partial reduction in pool level</p> <p>In some cases total draining and breaching are required for safety or are more economical</p>
(B) Embankment excessive seepage	<p>Seepage carries soil fines</p> <p>Sinkholes on embankment face</p> <p>Boulders</p> <p>Concentrated seepage</p> <p>Unusual wetness on embankment slope</p> <p>Unusually soft or quick embankment slope</p> <p>Marsh-type vegetation on embankment slope</p>	<p>Lack of appropriate internal drainage</p> <p>Inadequate core or cutoff</p> <p>Inappropriate embankment material</p> <p>Layering of relatively permeable zones in embankment</p> <p>Inadequate compaction</p> <p>Clogging of drains or filters</p> <p>Burrows caused by muskrats, beavers, groundhogs, foxes, moles, chipmunks</p> <p>Surface erosion gullies intersecting seepage zone</p> <p>Temporary saturation due to rain storms, snowmelt</p> <p>Seepage into, out of, or along conduits and drains</p>	<p>Dam failure by internal erosion</p> <p>Structural failure due to uplift of embankment or appurtenant structures</p> <p>Loss of storage</p>	<p>Distinguishing unsafe seepage from normal seepage requires considerable judgment. Amount of change in the rate of seepage is an important factor. May require installation of piezometers to help determine seriousness. Highly concentrated seepage or evidence of internal erosion or mass movement definitely requires treatment. If it appears that seepage line is high enough to threaten mass stability, consider steps under mass movement above. If mass movement is not indicated, a filtered drain in the crest(s) of concern is usually most appropriate. Other alternatives:</p> <p>Upstream seepage barrier (blanket)</p> <p>Install seepage cutoff beneath crest, such as slurry wall, thin membrane wall, grouting</p> <p>Filtered relief walls</p> <p>Fill gullies with filtered drain, riprap, prevent further erosion</p> <p>Remove trees, replace soil</p> <p>Trap and remove animals</p> <p>In some cases total draining and breaching is the most economical safe action</p>

Figure B12. Evaluation matrix of embankment dams

Defect	Possible Indicators	Possible Causes	Effects	Potential Remedial Measures
(C) Foundation movement	Heave of foundation near embankment toe Sinkholes Transverse or longitudinal cracks in embankment Sags in dam crest	Consolidation settlement Collapse of cavities (limestone terrane) Shear failure (usually occurs during construction and then is usually not a problem with existing dams) Liquefaction Earthquakes	Embankment failure due to loss of support, cracking, piping, mass movement Misalignment of appurtenant structures Cracking of appurtenant structures Loss of freeboard (storage) due to sags in crest	Increase embankment mass with free-draining mass downstream addition (subsurface data needed for optimal safe design) Regrade crest Realign appurtenant structures Repair appurtenant structures
(D) Foundation excessive seepage	Seepage carrying soil fines Sinkholes Boils at toe and downstream Concentrated seepage Unusually soft or quick ground	Inadequate cutoff (Re)opening of cavities (limestone terrane) Cracks due to differential settlement Fractures in foundation rock or soils	Embankment failure due to internal erosion in foundation, loss of support, collapse Loss of storage	See measures for embankment seepage (above) Downstream filtered drain trench or relief wells Upstream blanket Grouting Slurry wall or membrane Permanent reduction in reservoir pool level
(E) Unprotected slopes	Obvious visual indicators	Underused material Disintegrating riprap Surface not properly graded Obstructed or improperly located surface drain outfalls	Deep gullving Beeched upstream slope Reduced cross section can cause structural or seepage failure	Place or augment riprap Backfill and regrade surface Place granular downstream slope protection Realign and extend discharge of spillway and surface drains as required

Figure B12. (Continued)

APPENDIX C: CHECKLISTS AND EXPLANATORY
MATERIALS FOR SPILLWAYS, STILLING
BASINS, AND OUTLET WORKS

PERSONNEL	_____	_____	DATE	_____
	_____	_____	POOL	_____ TAIL _____
	_____	_____	PRECIP.	_____

INSTRUMENTATION

SLOPE INDICATORS _____

PIEZOMETERS _____

OBSERVATION WELLS _____

SURFACE REF. PTS. _____

UPSTREAM RIGHT ABUTMENT

FLOW OF GROUNDWATER _____ NATURAL SLOPE _____

CONDITION OF RIPRAP FOR DISPLACEMENT _____ DURABILITY _____

UPSTREAM DAM SLOPE

CONDITION OF RIPRAP FOR DISPLACEMENT _____ DURABILITY _____

UNIFORMITY _____ BERM _____

UPSTREAM LEFT ABUTMENT

CONDITION OF RIPRAP FOR DISPLACEMENT _____ DURABILITY _____

DITCH _____ NATURAL SLOPE _____

DOWNSTREAM LEFT ABUTMENT

RIPRAPPED DITCH _____ NATURAL SLOPE _____

DOWNSTREAM DAM SLOPE

COVER _____ UNIFORMITY _____ RIPRAP AT TOE _____

EROSION _____ SEEPAGE _____ EXIT OF SAND DRAIN _____

DOWNSTREAM RIGHT ABUTMENT

RIPRAPPED DITCH _____ NATURAL SLOPE _____

DISCHARGE CHANNEL

CONDITION OF RIPRAP FOR DISPLACEMENT _____ DURABILITY _____

TOP OF DAM

UNIFORMITY _____ CRACKS _____ SETTLEMENT _____

SPILLWAY CUT SLOPES

UPSTREAM RIGHT SIDE	_____	HORIZONTAL DRAINS	_____
DOWNSTREAM LEFT SIDE	_____	HORIZONTAL DRAINS	_____
DOWNSTREAM RIGHT SIDE	_____	HORIZONTAL DRAINS	_____
DISCHARGE CHAN. RT. SIDE	_____	HORIZONTAL DRAINS	_____

Figure C1. Checklist for embankment and cut slopes

SPILLWAY:

GENERAL

OGEE WEIR

GRAVITY WALLS

PAVED CHUTE

CHUTE WALLS

Figure C1. (Continued)

Spillway

Approach channel

Channel

Log boom

Control structures

Crest

Walls

Apron

Chute

Walls

Floor

Drains

Stilling basin

Walls

Floor

Outlet channel

Riprap

Erosion

Vegetation

Structural

Hoist deck

Bridge

Gates

Mechanical features

Hoists

Cables

Gates

Protective coatings

Figure C2. Checklist on spillways (Bureau of Reclamation)

Outlet Works

Inlet structure	_____
Trashracks	_____
Concrete	_____
Gate chamber	_____
Gates	
Operation at time of examination	_____
Exercising frequency	_____
Mechanical	_____
Electrical	_____
Protective coatings	_____
Posted operating instructions	_____
Ventilation	_____
Seepage	_____
Concrete	_____
Access tunnel	_____
Concrete	_____
Metalwork	_____
Outlet conduit	_____
Metalwork	_____
Protective coatings	_____
Concrete	_____
Cavitation	_____

Figure C2. (Continued) Outlet works (Bureau of Reclamation RO&M Program)

Control facilities	_____
Control house	_____
Structural condition	_____
Roof	_____
Walls	_____
Housekeeping	_____
Metalwork	_____
Protective coatings	_____
Gates	_____
Operation at time of examination	_____
Exercising frequency	_____
Mechanical	_____
Electrical	_____
Protective coatings	_____
Posted operating instructions	_____
Chute	_____
Floor	_____
Walls	_____
Drains.	_____
Stilling basin	_____
Outlet channel	_____
Vegetation	_____
Gravel bars, etc.	_____

Figure C2. (Continued)

SPILLWAY

CONTROL STRUCTURES

Crest _____
Orifices _____

GATES AND CONTROLS

Type of gate _____
General condition _____
Protective coatings _____
Leakage (closed) _____
Escrowing frequency _____
Operation of gates at _____
time of examination _____

CONTROLS FOR GATES

Mechanical _____

Hoists _____
Wire ropes _____
Protective coatings _____

Electrical _____

Remote control _____
Power supply _____
Sewerly power _____
Operation instructions _____

WEATHER DOORS

General condition _____
Protective coatings _____
Escrowing frequency _____
Operation at time _____
of examination _____

CONTROLS FOR WEATHER DOORS

Mechanical _____

Hoists _____
Wire ropes _____
Protective coatings _____

Electrical _____

STOPLOGS

General condition _____
Protective coatings _____
Seals _____

STILLING BASIN

Walls _____
Floor _____
Weir _____
River channel below basin _____

Riprap _____
Erosion _____
Vegetation _____

APPROACH CHANNEL

Vegetation (trees, willows, etc.) _____
Debris _____
Slides above channel _____
Channel side slope stability _____
Log booms _____
Slope protection _____

CONTROL STRUCTURES (OBSERVED OPERATION)

Apron _____

Surface condition _____
General condition of concrete _____
Movement _____
Settlement _____
Joints _____
Cracks _____

Crest _____

Surface condition _____
General condition of concrete _____
Cracks or areas of distress _____
Signs of movement _____

Walls _____

Surface condition _____
General condition of concrete _____
Movement (offsets) _____
Cracks or areas of distress _____
Settlement _____
Joints _____
Drains _____
Backfill _____

Gates _____

Condition _____
Hoist equipment _____
Control equipment _____

CHUTE OR TUNNEL

Debris _____
Walls _____

Surface condition _____
General condition of concrete _____
Movement (offsets) _____
Settlement _____
Joints _____
Cracks or areas of distress _____
Condition of backfill _____

Floor _____

Surface condition _____
General condition of concrete _____

Figure C3. Spillways (Bureau of Reclamation - SEED Program)

OUTLET WORKS

INTAKE

Trashrack
Concrete

OUTLET CONDUIT

Manhole
Cavitation

CONTROL FACILITIES

Gatehouse
Crane
Gate and controls

OUTLET CHANNEL

Vegetation
Gravel bars, etc.
Riprap
Stability of side slopes

OTHER

POWER FEATURES

(If related to safe operation or structural integrity of dam)

General condition
Protective coating
Cavitation
Excavating frequency
Operation at time
of construction
Control system

Remote
Auxiliary power
Mechanical
Electrical
Operating instructions

Weather barrier

General condition
Protective coating
Excavating frequency
Operation at time
of construction
Control

Bulkhead

Availability
General condition
Protective coating
Seals

STILLING BASIN

Debris in basin
Walls

Surface condition
Concrete
Joints
Cracks
Backfill
Movement

INTAKE STRUCTURE

TRASHRACK

BULKHEAD GATE

INTAKE GATES

INTAKE GATE HOISTS

GANTRY CRANE

Mechanical
Electrical
Fuel
Operating instructions
Operation during
construction
Maintenance

PENSTOCK

Powerplant structure
Ceilings
Deck

Floor (if visible)

Surface condition
Stainless steel liner
Concrete
Joints
Signs of deterioration
Cracks
Cavitation
Movement

Figure C3. (Continued) Outlet works and power features
(SEED Program)

PIERS

	S	U	REMARKS
SURFACE CONDITION	x		
CRACKS / SPALLS	x		
JOINT CONDITION	x		
ADDITIONAL REMARKS:			

GALLERY, EL 1002± - BLOCKS 37 THRU 43

	S	U	REMARKS
SURFACE CONDITION	x		
CRACKS / SPALLS	x		
JOINT CONDITION	x		
ADDITIONAL REMARKS:			

SLUICE GATE GALLERY, EL 880± - BLOCKS 37 THRU 44

	S	U	REMARKS
SURFACE CONDITION	x		
CRACKS / SPALLS	x		
JOINT CONDITION	x		
LEAKAGE	x		
ADDITIONAL REMARKS:			

Figure C4. Checklist on spillway
(Tennessee Valley Authority)

DAM INSPECTION CHECKLIST				Date _____	Time _____	
NAME OF DAM _____						
FILE NUMBER _____			INSPECTORS _____			
CHECK AREA	AS INSPECTED	SPILLWAYS • DRAINS • OUTLETS			ACTION	
		CHECK/CIRCLE CONDITION NOTED	OBSERVATIONS		REPAIR	MONITOR INVESTIGATE
FLOW-TO- INLET- RISER	Principal Spillway		Type:			
	train tracks/cables					
	gates/flashboards					
	cracks/deterioration					
	improper alignment					
	cracks/deterioration					
	joint deterioration					
	type					
	cracks/deterioration					
	seepage/dripping					
STILLING BASIN/OUTLET WAY	Emergency Spillway		Type:			
	vegetation/cover					
	erosion					
	obstructions					
	Lake Drains/Other Outlets		Type:			
	gates/valves					
	joints/flow surface					
	inlet tower					
	outlet area					
	operability					
TOE DRAIN OUTLETS	flow amounts					
	flow clear/muddy					
GENERAL COMMENTS, SKETCHES & FIELD MEASUREMENTS						

Figure C5. Checklist on spillway (ODNR)

THE PRINCIPAL SPILLWAY

Yes No

- | | | |
|---|--|--|
| <input type="checkbox"/> <input type="checkbox"/> Can water flow into the principal spillway without difficulty, as intended when constructed? | <i>The riser, intake structure, or channel should be free of trash or other blockage.</i> | <i>Install a trash rack if one is not already in place. Periodically clear trash racks of any accumulated debris.</i> |
| <input type="checkbox"/> <input type="checkbox"/> Is outlet pipe or discharge channel clear and open to allow the free passage of the principal spillway discharge? | Flows passing through the spillway should not erode or otherwise damage the dam. | Keep outlet pipe, plunge pool, and all other outlet works clear and in good repair. |
| <input type="checkbox"/> <input type="checkbox"/> Is the primary spillway structure in good condition (check concrete, wood, and metal portions for damage or deterioration)? | Such dam features as the principal spillway require continued maintenance like any other structure. | Repair and maintain as appropriate to insure the continued useful life of the dam. |
| <input type="checkbox"/> <input type="checkbox"/> Does the lake have a drain that can be used to lower it in an emergency? | Lowering a lake may be necessary if the dam begins to develop problems. | Check plans or search dam for emergency drain system. |
| <input type="checkbox"/> <input type="checkbox"/> If there is an emergency drain, is it known to be in working condition? Note: If a drain has not been used for a long time, it may be possible to open it but not close it. | Drain valves and other mechanisms should receive sufficient maintenance to insure that they remain in working order. | Maintain system so that it can be used in an emergency. Normally, the pool behind an earth embankment dam should not be lowered at a rate of more than 6 inches a day. |
| <input type="checkbox"/> <input type="checkbox"/> If there are other gates, valves, or operating equipment, are these in working condition? | Such devices are vital to the effective and safe operation of the dam. | Repair and restore if necessary, and maintain in an operable condition. |

THE EMERGENCY SPILLWAY

- | | | |
|--|--|---|
| <input type="checkbox"/> <input type="checkbox"/> Can water flow into the emergency spillway without difficulty, as intended when constructed? | <i>To be effective, all portions of the spillway channel should be clear and unobstructed.</i> | <i>The approach channel should be kept free of trash, underbrush, or other blockage.</i> |
| <input type="checkbox"/> <input type="checkbox"/> Is the discharge channel clear and open to allow the free passage of the emergency spillway discharge? | Spillway flows must be effectively conducted away from the dam. | Clear as necessary. |
| <input type="checkbox"/> <input type="checkbox"/> Is the emergency spillway constructed in such a way that its flows will not erode other portions of the dam? | A berm is often constructed to keep spillway flows from flowing down the embankment. | Reshape dam if necessary to take care of this problem. |
| <input type="checkbox"/> <input type="checkbox"/> Is the emergency spillway in good condition overall (check for erosion within the channel, adequacy of grass cover, etc.)? | <i>Spillway erosion is a common problem.</i> | <i>Restore any erosion gullies or eroded areas. Provide channel protection (riprap, concrete, etc.) if necessary to eliminate recurring erosion problems.</i> |

Figure C6. Principal spillway (Virginia Bureau of Water Control Management)

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL		
APPROACH CHANNEL		
DISCHARGE CHANNEL		
BRIDGE AND PIERS		
GATES AND OPERATION EQUIPMENT		

Figure C7. Gated spillway (Pennsylvania Department of Environmental Resources)

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT		
INTAKE STRUCTURE		
OUTLET STRUCTURE		
OUTLET CHANNEL		
EMERGENCY GATE		

Figure C7. (Continued) Outlet works (Pennsylvania Department of
Environmental Resources)

Satisfactory-No Change Requires Work or Further Investigation	Date Corrected	Job Number	
			3. Spillway
			*a) Erosion, undercutting, restrictions
			b) Debris in spillway or spill channel
			*c) Downstream encroachments in spill channel
			*d) Energy dissipator, flip bucket (visual to extent possible)
			e) Flashboards - maximum height, condition, security, when they can be installed (Bull. #54)
			2) Radial, drum, or slide gates - condition of gates, seals, chains, cables, hoist operators; periodic operation (Bull. #35)
			g) Electrical and other mechanical equipment-maintenance, operation
			h) Log boom - submergence, condition, continuity, anchors
			i) Lubrication - gate trunnions, chain links, cables, operators (Bull. #6)
			j) Siphons - clear of obstructions
			4. Fish ladder and screens-operation, gravel intrusion, condition
			5. General concrete deterioration
			6. Protective paints and coatings, particularly on submerged facilities
			7. Employee and public safety
			8. Signs, including General Recreation Warning, Maximum Water Surface, etc.
			9. Housekeeping
			10. Security - fencing, locks, unauthorized entry
			11. Fish release facilities and requirements - verify flow

Figure C8. Dams and reservoirs (PG&E)

WATER COLLECTION INSPECTION CHECKLIST

FACILITY _____ DATE _____

INSPECTOR _____

Notes: The items listed below are to be inspected to determine if a change has occurred or an unusual condition exists that requires maintenance, improvement, or further investigation. On items marked with an asterisk (*), notify G. O. Hydro Generation Department of any adverse condition.

1. Intake

- a. Log boom - submergence, condition, continuity, anchors
- b. Trash rack - clear of debris
- c. Trash rake - operation, maintenance
- d. Water surface staff gage, recorder, floatwells
- e. Excess flow device - operation, settings, pitot tube flushing
- f. Heaters
- g. Gates - condition and operability, to include electrical and mechanical equipment; is gate at proper elevation; periodic operation
- h. Cables - condition and protective coatings
- i. Lubrication (Bull. #6)
- j. Standby motor generator - maintenance, operation
- k. Security - fencing, locks, unauthorized entry
- l. Communication equipment and alarms - operability
- m. Batteries and charger - corrosion, water
- n. Housekeeping
- o. Vortexing or unusual sounds
- p. Structural stability - cracks, movement
- q. Operator and accumulator tank
- r. Other electrical and mechanical equipment
- s. Operating instructions

Figure C8. (Continued) Tunnels (PG&E)

Satisfactory-No Change
Requires Work or
Further Investigation
Date Corrected
Job Number

2. Surge Chamber

- a. Road access
- b. Security - fencing, locks, unauthorized entry
- c. Spillway - erosion, undercutting, restrictions, encroachments
- d. Leakage

3. Adits and Portals

- a. Road access
- b. Security - fencing, locks, unauthorized entry
- c. Drain and sand/rock trap - operation, flushing

*4. Leakage, wet spots - at portals, adits, and along alignment

*5. Unauthorized activities in vicinity of tunnel - logging, roads, drilling, blasting, etc.

6. Ground conditions near tunnels

Notes:

Figure C8. (Continued)

Type of Defect	Causes	Effects	Remedies	Type of Defect	Causes	Effects	Remedies
Defective spillways and outlets	Insufficient analysis	Overflowing or erosion or washout on downstream	Re-evaluate spillway capacity using present day hydrologic techniques	Differential foundation settlement	Trunk and debris	Gates becoming inoperable	Regulate foundation
	Design error		Use watershed model simulation and prototype studies in design				
	New criteria established	Failure along and around spillway chute	Indicate major repairs: Increase spillway capacity				
Excessive trash/ debris	Major or unexpected events	Block	Construct a of auxiliary or emergency alternate methods	Surface irregularities (offset joints, voids, transverse grooves, roughness)	Cavitation erosion	Piping	Grinding surface to smoothness that will prevent cavitation erosion
			Re-evaluate spillway capacity				
			Re-evaluate spillway capacity				
Defective gates and bents	Excess trash/ debris	Overflowing or erosion or washout on downstream	Re-evaluate spillway capacity	Unbalanced flow (can cause other problems to occur, such as locking of steel linings and concrete erosion)	Air vents at irregularities	Regulate close construction tolerances	Provide adequate grout in close air into flowing water
			Re-evaluate spillway capacity				
			Re-evaluate spillway capacity				
Mechanical breakdown	Damage to trash racks	Damage to trash racks	Perform regular maintenance on mechanical equipment	Sealing in conduit	Structural vibrations	Cavitation	Perform prototype studies and modify
			Perform regular maintenance on mechanical equipment				
			Perform regular maintenance on mechanical equipment				
Cavitation around gate guides	Damage to gate frames and guides	Damage to gate frames and guides	Check bottom gate seal for damage	Unsymmetrical flow	Erosion in stilling basins	Point separation	Install guide vanes
			Provide for sharp turn flow breakoff				
			Repair cavitated areas with steel liners, check that all gate frames are securely mounted				

Figure C9. Evaluation matrix of appurtenant structures
(Safety of Existing Dams)

Type of Defect	Causes	Effects	Remedies
Defective drainage system	Inadequate design, improper installation	Uncontrolled seepage, piping, floods	Investigate and modify existing drain flint. Provide relief wells. Reduce reservoir pond level. Improve filter layer.
	Inadequate filter layer	Saturated conditions, seepage of fine silt from foundation, clogging	Remove slabs. Drill supply manual drains. Increase thickness of concrete slabs. Impose tailwater elevation that will force hydraulic pump.
Erosion	Mineral deposition	Fluctuating positive to negative or uplift pressures, can develop on spillways and stilling basins	Provide floor drain openings in locations to avoid subjecting them to fluctuating pressures.
	Inadequate design of spillways and stilling basins	Cracking of concrete slabs in stilling basins and subsequent removal of embankment material, this fluctuation of pressures can demolish a spillway or stilling basin	Pressure grout cracks in slab. Replace with thicker slab.
Structural cracks in concrete slabs of spillways and stilling basins	Water seepage through slab and embankment materials	Development of voids under slab, loss of slab support, break-up of slab	Evaluate effectiveness of energy dissipators and replace if necessary. Fill voids under concrete slabs.
	Unsymmetrical operation of tail gate	Uneven loading of spillway, scour actions in the bays, etc.	Anchor invert. Operate gates symmetrically. Repair with erosion resistant aggregate and high strength concrete.
Type of Defect	Causes	Effects	Remedies
	Excessive discharges, abrasive objects in stilling basins, boulders, construction debris, etc.	Abrasion and cavitation erosion of concrete in spillway and stilling basins	Repair with special concrete and steel plates. Use dischargers with steel plates.
Type of Defect	Causes	Effects	Remedies
	Damage to chute blocks and energy dissipators	Breakup of slabs and destruction of spillway	Install rip rap.
Type of Defect	Causes	Effects	Remedies
	Overtopping is more critical on earth or rock-filled dams. Concrete dams can stand a limited amount of overtopping.		
	Large trash, such as logs, etc., can damage spillways, stilling basins, and energy dissipating blocks as it is carried over the spillway.		
Type of Defect	Causes	Effects	Remedies
	New techniques for repair, polymer impregnated concrete has been used to repair cavitation in concrete tunnels and stilling basins.		
	New technique for repair: for spillway repair, rollercrete has been used as an alternative repair method.		

Figure C9. (Continued)

APPENDIX D: CHECKLISTS AND EXPLANATORY
MATERIALS FOR LOCKS, LOCKWALLS,
LOCKGATES, AND OPERATING EQUIPMENT

P - M RECORD

EQUIPMENT

COMPRESSOR, AIR 300# NO 2

COMPONENT

GENERATOR GOVERNOR SYSTEM

LOCATION

NO. _____

POWERHOUSE +37 by UNIT #6 CARD NO. _____

REPORT MADE		YES NO	REMARKS PREVENTIVE MAINTENANCE INSPECTIONS AND TROUBLE REPORTS CHARGED TO STANDING MAINTENANCE ORDERS	INSPECTIONS	
E-M-G OR TR	DATE			MAN-HOURS	BY
TR	4-16-77		COMPRESSOR WOULD NOT START, RAISED COOLING WATER FLOW	1	AN
F	8-30-77		PMED 47.4 HRS	1	LR
TR	12-27-77		TRIPPED AT FLOWING LEAKS AT MOTOR DISCONNECTED AND SHORTED TO MOTOR CASE. REPAIRED MOTOR MESSAGES TO GO		
TR	2-23-78		COMPRESSOR TRIPPED 3 TIMES COULD FIND NOTHING WRONG	2	LMH
TR	3-1-78		COMPRESSOR TRIPPED 3 TIMES COULD NOT FIND PROBLEM. CHECKED TEMP	2	AN
			DISCHARGE WATER HD DISCHARGE AIR 320° OIL PRESS 40 HPS RPM 2		
			DIFFERENT TIMES ONCE FOR 45 MIN AND ONCE FOR 50 MIN WITH NO TROUBLE	7	AN
PM	4-17-78	41	SERVICED OIL COOLERS COOL 161. HRS.	112	2452
E	4-17-78	E PM	" " " " " "	2	NAULT
E	2-24-78	PM	" " " " " "	1	41
PM	18 Dec 78	M	249.9-7mm 1st. drive - HRS. 261.4	4	AB
E	15 MAR 79	F	# 2 - BKR. KC 14 HM 2651 Oil pressure 40#	3	2W
E	6 Dec 79	E	316.5 - Inf.	42	RB
M	25 Dec 79	M	yard air breathes	3	28
M	9 Oct 79	M	350 J - 321.5 deg.	12	LC
E	7 Dec 80	E	117 383.6 deg.	1	AB
M	18 Dec 80	M	PM 11 2-35.0 deg.	2	28
			PM 11 384.3 deg.		

Figure D1. Portland/Walla Walla computer summary

12, 38

D3

GENERATOR GOVERNOR SYSTEM				P - M DATA CARD			
LOCATION				EQUIPMENT			
POWERHOUSE #37 BY UNIT				COMPRESSOR, AIR, 300# #2.			
MANUFACTURER				COMPONENT			
GARDNER DENVER CO.							
DATE INSTALLED	COST PER UNIT	CONTRACT OR P.O. NO.	ACCOUNT NO.				
1976	12,090.	Docw57-75-C-0219					
NAME PLATE DETAIL DESCRIPTION, REFERENCE DATA OPERATING LIMITATIONS				INSPECTION SCHEDULES			
				ELECT	MECH	GEN	
CONTROLS AT COMPRESSOR:							
EMERGENCY STOP SWITCH:							
SQUARE D CLASS 2510 TYPE FO-1 (BRINGS IN ALARM-COMPRESSOR TROUBLE)							
RELAY COIL #2959-S1 SQUARE D #33A SFO 120V 60HZ 100V 50 HZ							
TIMER: G.W. FAUGE SIGNAL DIVISION TYPE CG 60 A6 CODE 8K 25 SH 120V 60 HZ (BY PASSES OIL PRESSURE & LOADS COMPRESSOR)							
DISCHARGE FLOW SWITCH: McDONNELL & MILLER ITT Chicago USA McDonnell No. FS4-3 FLOW SWITCH UL LISTED 33137NI MAX PRESSURE 150 lbs MAX TEMP 300° F RATING IN AMPS 115 VAC 7.4 F.L. 44.4A L.R. 230 VAC 3.7A F.L. 22.2 L.R. 22							
PILOT DUTY RATING A.C. 125V.A. 115-230V							
DISCHARGE TEMP SWITCH: UNITED ELECTRICAL CONTROLS CO. WATERTOWN, MASSACHUSETTS, USA							
TYPE C 11				RANGE 0-225°F			
MODEL 102				MEG 9-75			
STOCK No. 9037				AMPS 15			
				VOLTS 125/250			
<i>photo interference</i>							
CONTINUE ON REVERSE SIDE							
NPD 113-1 (TEST)							

Figure D1. (Continued)

ILLINOIS WATERWAY, ILLINOIS
DRESDEN ISLAND LOCK AND DAM

INSPECTION CHECKLIST

INSPECTION PERSONNEL:

_____	_____
_____	_____
_____	_____

DATE OF INSPECTION:

INSPECTION OBSERVATIONS:

1. LOCK:

General

Approach Walls

Concrete condition _____

Alignment _____

Joints _____

Other _____

Lock Walls

Concrete condition _____

Alignment _____

Joints _____

Other _____

Lower Gate Bays and Forebays

Concrete condition _____

Alignment _____

Joints _____

Other _____

Figure D2. Inspection checklist for lock and dam
(Rock Island District)

Miter Gates

General condition _____

Structural details _____

Seals _____

Operating machinery _____

Tainter Valves

General condition _____

Structural details _____

Seals _____

Operating machinery _____

2. DAM:

General _____

Piers

Concrete condition _____

Cracks (compare with photographic records) _____

Tainter Gates

General condition _____

Structural details _____

Seals _____

Operating machinery _____

Roller Gates

General condition _____

Figure D2. (Continued)

Roller Gates (cont'd)

Structural details _____

Rack and Rim and Guardrail _____

Seals _____

Operating machinery _____

Service Bridge

Steel Girders _____

Bracing _____

Structural details _____

Bearings _____

Deck _____

Storage Yard

Storage yard trestle _____

Bulkheads _____

Retaining walls _____

Other _____

Earth Dike

Submersible _____

Non-submersible _____

Figure D2. (Continued)

APPENDIX E: CHECKLISTS AND EXPLANATORY MATERIALS
FOR POWERHOUSES AND PUMPING PLANTS

RIN 10207A

NASHVILLE DISTRICT
POWERHOUSE EQUIPMENTPAGE NO 3
RUN DATE 30 MAY 84

LOCATION-J PERCY FRIEET

FOR MONTH OF --JUNE

***** THE FOLLOWING EQUIPMENT IS DUE THIS MONTH FOR ROUTINE INSPECTION *****

NO.	EQUIPMENT NAME	TYPE TEST	FREQ NO.	TEST DATE LAST	TEST DATE NEXT	ROUTINE TIME	SPECIAL TIME	SHEET OR GUIDE NO.
40053	HEADGATE CONT. BOS + PANELS 24MO	1	24	82/08	84/08	13	6	00014000
40058	DAM SUPP PUMP MOTOR CONT. NO. 1+2	1	3	84/03	84/08	72	109	00014000
40060	SUBMERGIBLE RAWWATER FWP MTR. IN DAM	1	3	84/03	84/08	59	12	00010000
40062	SUBMER. RAWWATER FWP MTR CONT IN DAM	1	3	84/03	84/08	59	55	00014000
40304	MAIN CONT BOS. & PANELS	7	24	82/08	84/08	20	6	14001
41001	STA. SER. TRANSF. TEMP. IND + RELAYS	1	24	82/08	84/08	7	6	00010021
41002	STA. SER. TRANSF. INTERNAL INSP.	1	24	82/08	84/08	36	6	00011007
41250	STA. TRANSF. ACB 214	1	24	82/08	84/08	30	6	00012003
41251	STA. TRANSF. LOAD BREAK DEC 213	1	24	82/08	84/08	10	6	00016003
41253	480 VOLT MAIN AUX. BOARD + ACB'S	7	24	82/08	84/08	73	8	00013000
41352	D.C. DISTRIBUTION SYSTEM 125 VOLT	1	6	83/12	84/08	47	28	00013000
41353	D.C. DISTRIBUTION SYSTEM 48 VOLT	1	6	83/12	84/08	11	7	00018006
41354	BATTERY CHARGER NO. 1+2 125 VOLT	1	24	82/08	84/08	22	6	00014000
41653	POWERHOUSE CRANE CONT. BOS + PANELS 24	1	24	82/08	84/08	33	7	00013000
41654	POWERHOUSE CRANE TROLLEY SYSTG	1	24	82/08	84/08	64	29	00013001
41802	STA. LIGHTING SW-GEAR PANELS + ENCLRS	1	6	83/12	84/08	28	27	00013012
41930	DRY CHEMICAL EXTINGUISHER	1	1	83/12	84/08	21	13	00014000
41986	PREFERRED AC SUPPLY + M.G. SET	1	12	82/08	84/08	76	53	00011021
42000	69 KV. TRANSF. CORR. GAS + OXYGEN TEST	1	3	84/03	84/08	56	6	00011024
42004	69 KV. TRANSF. BUSHINGS + INSULATORS	1	24	82/08	84/08	7	6	00011002
42150	69 KV. TRANSF. REACTOR INS. OIL	1	24	82/08	84/08	3	6	00011003
42151	69 KV. TRANSF. REACTOR BUSH. + INS.	1	24	82/08	84/08	11	6	00011002
42175	69 KV. TRANSF. AIRFOUR. SHELL + INCLRS.	1	24	82/08	84/08	8	6	00012011
42176	69 KV. TRANSF. LGT. ARR. CONN.	1	24	82/08	84/08	18	2	617-B
42386	RESOURCE DISTRIBUTION TRANSFORMER 1	1	36	81/08	84/08	19	2	617-B
42387	RESOURCE DISTRIBUTION TRANSFORMER 2	1	36	81/08	84/08	18	2	617-B
42388	RESOURCE DISTRIBUTION TRANSFORMER 3	1	36	81/08	84/08	16	13	617-B
42500	FREE SECURITY ELECTRICAL	1	3	84/03	84/08	30	27	000
43003	RUBBER BLANKETS ELECT TEST	1	6	83/12	84/08	31	59	000 2004
44002	SPILL GATE 1 CRANE + HOIST BRAKES	1	3	84/03	84/08	51	59	000 2004

Figure E1. Maintenance report for powerhouse equipment (Nashville District)

PREVENTIVE MAINTENANCE NOTIFICATION

INITIALS

DUE DATE DEC 1983 .) ()

SWITCHEBOARDS

WBL 7044

LOCATION MISC SUPPORT SYS

M/N

SERVICES REQUIRED

DATE (MO/YR) LBR HRS INSP CODE

DATE (MO/YR)	LBR HRS (HRS/MIN)	INSP CODE	SERVICES REQUIRED
4/18/84	2:40	HO	CHECK CONDITION OF WIRING, TERMINAL BLOCKS & CONNECTION
4/18/84	0:30	HP	CHECK CONDITION OF CONTROL SWITCHES
4/18/84	0:30	HQ	TEST OPERATE INFREQUENTLY USED SWITCHES
4/18/84	2:40	HR	INSPECT CONDITION OF INTERLOCK OR POSITIONING RELAYS
4/18/84	2:30	HS	INSPECT CONTACTS & MECH. CONTROLLED ELECT CONTACTORS
4/18/84	1:30	HT	CHECK FOR BURNING, FITTING, & CORROSION
4/18/84	0:30	HU	CHECK FOR PRESENCE OF DUST, RUST, & MOISTURE
4/18/84	1:45	HV	CHECK FOR PROPER AIR GAP, LOOSE CONNECTIONS, & WEAR
4/18/84	0:45	HW	CHECK FOR MISALIGNMENTS & FREEDOM OF MOVEMENT
4/18/84	0:30	HX	CHECK FOR LOOSE OR BROKEN SHADING RINGS
4/18/84	1:15	HY	CLEAN & LUBRICATE

Figure E2. Maintenance notification card (Nashville District)

PROJECT - 0 THE DALLIES DAM										DATA FOR SEP 20 DEC 82 13:31 PAGE									
PFY OCT NOV DEC JAN FEB MAR										APR MAY JUN JUL AUG SEP CF									
0044 RIN MAINS DERRICKSCRAHES										16									
1 MAINTENANCE CENTER - 2 THE DALLIES DAM CENTER										2									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO. MAINTENANCE ORDER										1									
0044 RIN MAINS DERRICKSCRAHES										16									
0 NO.																			

MAINTENANCE CENTER - 1 HONOLULU DAW CENTER			PROJECT - 1 HONOLULU DAW			DATA FOR SEP 1983												PAGE 1
W-1 MAINTENANCE ORDER	QTR CFY07	PFY	QTR	QTR	QTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	CFY			
						14									14			
LEVEES & PUMPING PLANTS	TOTAL		16			209	12								275			
POWER FACILITIES																		
5001 CUSTOMER INCL JANUARY 1983		524	214	102	04	112	107	171	111	96	111	93	40	107	524			
TCP=01		1231	155	104	04										1314			
TOTAL		524	214	102	04	112	107	171	111	96	111	93	40	107	524			
5002 RELIANCE INSTRUCTORS	ELFC	30	5	3	1	6	4	2	3	4	2	2	2	4	30			
TCP=010	ENTR	20	2	2	2		4		6	2				4	20			
TOTAL		7	5	5	3	6	4	2	9	6	2	2	2	4	50			
5003 RELIANCE OUTSIDE FIX	ELFC											16			19			
TCP=015	TOTAL											16			19			
5007 INDEPENDENT FIRE FIGHTING EQUIP	ELFC	24	11	2	6		2	3			2		4		29			
TCP=010	ENTR	29	4	14	10	7	12	4	26	11		10	6		63			
TOTAL		4	4						4	2		4		8	59			
5011 FILE PURCHASE, GOV. HYDROGEN OILS	ELFC	14	18	18	10	13	14	7	30	13	2	26	10	8	170			
TCP=010	ENTR																	
TOTAL																		
5021 PH CAPD INSP OF STRUCTURES	ELFC	146	7	13	25										146			
TCP=010	ENTR																	

Figure E3. (Continued)

Structural features

Building (wood, concrete, metal
construction)

Walls

Roof

Decks

Drainage

Crane

Doors, windows

Ventilation

Lighting

Safety

Forebay conditions

Inlet channel

Concrete

Riprap

Debris or silt bars

Trashracks

Stoplogs and grooves

Sump conditions

Other metalwork

Pumping units

Maintenance procedures

Vibration

Cavitation

Lubrication

Bearing temperatures

Figure E4. Checklist for major pumping facilities (RO&M)

Pumping units - Continued

Packing box leakage	_____
Paint deterioration	_____
Unit mounting and foundation	_____
Low water cutoff system	_____
Pump priming system	_____
Other operating difficulties	_____
Discharge valves (manual, motor, or hydraulic-operated)	_____
Operation	_____
Vibration	_____
Maintenance procedures	_____
Lubrication	_____
Paint deterioration	_____
Unit mounting and foundation	_____
Electrical control equipment	_____
Housekeeping (clean and dry)	_____
Protective coatings	_____
Maintenance procedures	_____
Other operating difficulties	_____
Afterbay conditions	_____
Discharge piping	_____
Interior	_____
Exterior	_____
Anchor blocks	_____
Discharge boxes	_____
Flap valves	_____
Other metalwork	_____

Figure E4. (Continued)

POWER FEATURES

(If related to safe operation or structural integrity of dam)

INTAKE STRUCTURE _____

TRASHRACK _____

BULKHEAD GATE _____

INTAKE GATES _____

INTAKE GATE HOISTS _____

GANTRY CRANE

Mechanical _____

Electrical _____

Paint _____

Operating instructions _____

Operation during _____

examination _____

Storage area _____

PENSTOCK

Powerplant structure _____

Ceilings _____

Deck _____

Walls _____

Substructure _____

TAILRACE

Draft tube closure structure _____

Draft tube bulkhead _____

Gantry crane _____

STANDBY POWER UNIT

Condition _____

Exercising frequency _____

Automatic features _____

Operation during examination _____

OTHER

Figure E5. Power features (Bureau of
Reclamation - SEED Program)

INSTRUMENTATION

1. Monumentation/Surveys _____

2. Observation Wells _____

3. Weirs _____

4. Piezometers _____

5. Stream Gage Recorder _____

6. Other _____

RESERVOIR

1. Slope _____

2. Bank _____

3. Sedimentation _____

4. Other _____

Figure E6. Instrumentation (Kansas Division
of Water Resources)

[illegible]

Remarks: _____

Tested By: _____ Assisted By: _____

1. DATE: _____

2. FACILITY: _____

3. LOCATION: _____

4. DESCRIPTION OF DAMAGE: _____

5. DAMAGE CAUSED BY:

A. TYPE OF EQUIPMENT: _____

B. OWNER OF EQUIPMENT: _____

6. PROPOSED METHOD OF REPAIR _____

7. ARE EMERGENCY REPAIRS REQUIRED: _____

8. ESTIMATED COST OF DAMAGE OR REPAIRS: _____

9. REMARKS: _____

DATE OF REPORT: _____ SIGNED: _____

E10

APPENDIX F: CHECKLISTS AND EXPLANATORY MATERIALS
FOR BRIDGES AND ROADS

OVERALL DESCRIPTION		UNABRIDGED DESCRIPTION		SUBJECTIVE DESCRIPTION	
New Condition		New Condition		Good	The item is new or in good condition--no repairs necessary.
3	Good condition --no repair necessary	No repair necessary. No sign of distress or deterioration		Fair	The item is still performing the function for which intended. In need of minor repair.
4	Minor items in need of repair	Includes all preventive maintenance work on any type element. A defective or deteriorated secondary-type element that probably will not progress to a serious defect if not repaired within a reasonable period of time. Includes progressive deterioration that can lead to possible failure, and can be arrested by maintenance repair. A defective or deteriorated major structural element vital to structural integrity of the bridge.		Poor	The item is still performing the function for which intended but at a minimum level. The item is in need of major repair.
5	Major items in need of repair	Same as for 4 except that extent of deterioration is greater and repair may require complicated and/or extensive procedures. Major rehabilitation needed.		Critical	The item is not performing the function for which intended.
6	Major repair project needed	Major structural element is marginally adequate to support unrestricted legal load-potential should be considered. Continued observation indicates that failure is not progressive under restricted loading. This rating is relative to the class of loading using the bridge.			
7	Minimum adequacy to tolerate present traffic--immediate rehabilitation necessary to keep open	Major structural element deteriorated or damaged so as to reduce its capability of carrying trucks. Allow light loads only if stress check warrants and continued observation indicates failure is not progressive under light loads. Considered inadequate to tolerate legal loads and should be posted for light loads.			
8	Inadequate to tolerate present heavy load-warrants closing bridge to trucks	Major structural element deteriorated or damaged so as to reduce its capability of carrying any loads. Stress check indicates structure cannot support any live load. Bridge should be closed.			
9	Inadequate to tolerate any live load-warrants closing bridge to all traffic	Bridge closed. Bridge can be reopened with a complete rehabilitation.			
10	Bridge repairable if desirable to reopen to traffic	Bridge closed. Bridge conditions are beyond repair and in danger of immediate collapse. Keep bridge closed.			
11	Bridge conditions beyond repair--danger of immediate collapse				

Figure F1. Condition rating (Federal Highway Bridge Replacement and Rehabilitation Program)

Federal-aid Highway Program Manual 6-7-2-7	Overall Description		Condition Indicators (% deck area)			
	Rating	Condition	Spalls	Delam- inations	Electrical Potential	Chloride Content #/CY
Category #3 Light Deterioration	9	New condition	none	none	0	0
	8	Good condition - no repair necessary	none	none	none > 0.35	none > 1.0
	7	Minor items need repair	none	< 2%	45% < 0.35	none > 2.0
Category #2 Moderate Deterioration	6	Major items need repair	< 2% spalls or sum of all deteriorated and/or contaminated deck concrete < 20%			
	5	Major repair project needed	< 5% spalls or sum of all deteriorated and/or contaminated deck concrete 20 to 40%			
Category #1 Extensive Deterioration	4	Minimum adequate to tolerate present traffic	> 5% spalls or sum of all deteriorated and/or contaminated deck concrete 40 to 60%			
	3	Inadequate for heavy truck loads, warrants closing bridge to truck traffic	> 5% spalls or sum of all deteriorated and/or contaminated deck concrete > 60%			
Structurally Inadequate Deck	2	Inadequate to tolerate any live load - warrants closing to all traffic	Deck structural capacity grossly inadequate			
	1	Closed bridge repairable if desired to reopen to traffic	Deck has failed completely Repairable by replacement only			
	0	Bridge beyond repair - danger of immediate collapse	Holes in deck - danger of other sections of deck falling			

Figure F1. (Continued)

TEXAS HIGHWAY DEPARTMENT

DISTRICT _____ COUNTY _____ CONTROL _____ SECTION _____ STRUCTURE NO. _____ HIGHWAY _____

DESCRIPTION _____

INSPECTOR'S SIGNATURE _____ DATE _____

<p>CONDITION RATING</p> <p>9 <u> </u> New Condition</p> <p>8 <u> </u> Good condition - no repair necessary</p> <p>7 <u> </u> Minor items in need of repair</p> <p>6 <u> </u> Major items in need of repair</p> <p>5 <u> </u> Major repair project needed</p> <p>4 <u> </u> Minimum adequacy to tolerate present traffic, immediate rehabilitation necessary to keep open</p> <p>3 <u> </u> Inadequacy to tolerate present heavy load - warrants closing bridge to trucks</p> <p>2 <u> </u> Inadequacy to tolerate any live load - warrants closing bridge to all traffic</p> <p>1 <u> </u> Bridge repairable. If desirable to reopen to traffic</p> <p>0 <u> </u> Bridge conditions beyond repair - danger of immediate collapse</p> <p>N <u> </u> Not Applicable</p> <p>NOTES: Enter a rating for each element of each component. Then enter an overall rating for the component. Fully supportive comments are to be made hereon or on attachments for all ratings of 7 or below.</p>	<p>ROADWAY</p>
<p>Wearing Surface _____</p> <p>Deck _____</p> <p>Joints, Expansion, Open _____</p> <p>Joints, Expansion, Sealed _____</p> <p>Joints, Other _____</p> <p>Drainage System _____</p> <p>Curbs, Sidewalks & Parapets _____</p> <p>Median and/or Barrier _____</p> <p>Railings _____</p> <p>Railing Protective Coating _____</p> <p>Delineation _____</p> <p>Other _____</p> <p align="right">Roadway Component Rating </p> <p align="right">Comments:</p>	<p>SUPERSTRUCTURE</p> <p align="right">Condition Rating </p> <p>Main Members - Steel _____</p> <p>Main Members - Concrete _____</p> <p>Main Members - Concrete, Prest. _____</p> <p>Main Member Connections _____</p> <p>Secondary Members _____</p> <p>Floor System Members _____</p> <p>Other Connections _____</p> <p>Expansion Bearings _____</p> <p>Fixed Bearings _____</p> <p>Steel Protective Coating _____</p> <p>Other _____</p> <p align="right">Superstructure Component Rating </p> <p align="right">Comments:</p>

Figure F1. (Continued)

The sufficiency rating formula described herein is a method of evaluating factors, which are indicative of bridge sufficiency to remain in service. The result of this method is a percentage in which 100 percent would represent an entirely sufficient bridge and zero percent would represent an entirely insufficient or deficient bridge.

Ratings calculated by this formula are used by the Federal Highway Administration (FHWA) for selection of candidate bridges for the Federal Highway Bridge Replacement and Rehabilitation Program. However, prior to calculation of this rating for a given structure, the bridge is first determined to be either "Structurally Deficient" or "Functionally Obsolete". Bridges not falling into one of these two categories are not selected as candidates. Bridges with sufficiency ratings less than 50.0 are eligible for replacement or rehabilitation, and those with ratings of 80.0 or less are eligible for rehabilitation. The structurally deficient and functionally obsolete categories are defined as follows:

Structurally Deficient

1. A condition rating of 4 or less for
Item 58 - Roadway; or
Item 59 - Superstructures; or
Item 60 - Substructures
- or 2. An appraisal rating of 2 or less for
Item 67 - Structural Condition; or
Item 71 - Waterway Adequacy.¹

Functionally Obsolete

1. An appraisal rating of 3 or less for
Item 68 - Roadway Geometry; or
Item 69 - Underclearances;² or
Item 72 - Approach Roadway Alignment.
- or 2. An appraisal rating of 3 for
Item 67 - Structural Condition; or
Item 71 - Waterway Adequacy.¹

Any bridge classified as structurally deficient is excluded from the functionally obsolete category.

NOTES: ¹ Item 71 applies only if the last digit of Item 42 is coded
0, 5, 6, 7, 8 or 9.

² Item 69 applies only if the last digit of Item 42 is coded
0, 1, 2, 4, 6, 7 or 8.

Figure F1. (Continued)




Figure F2. PCI scale and condition rating (PAVER)

REPORT DATE- 06/06/81

PCI REPORT

INSTALLATION NUMBER = 051215

FORT EUSTIS

BRANCH NUMBER	BRANCH USE	SECTION NUMBER	PCI	RATING	SURFACE TYPE	SECTION AREA/SY	PAVEMENT RANK
IMONR	ROADWAY	01	50	FAIR	AC	408	TERTIARY
	11/27/79	[FROM] NR BLDG 832			[TO] W EDGE LUCAS PL		
IBUTN	ROADWAY	02	52	FAIR	AC	392	TERTIARY
	11/08/79	[FROM] E EDGE PATTON AVE			[TO] W EDGE PERSHING AVE		
IMULB	ROADWAY	04	52	FAIR	AC	1683	TERTIARY
	02/20/80	[FROM] NR BLDG 3905			[TO] END OF PAVEMENT		
I12ST	ROADWAY	03	52	FAIR	AC	399	TERTIARY
	02/11/81	[FROM] E'LY EDGE PATTON			[TO] W'LY EDGE LEE BLVD		
IDICK	ROADWAY	01	53	FAIR	AC	964	TERTIARY
	12/03/79	[FROM] S EDGE LEE BLVD			[TO] N EDGE TYLER AVE		
IREIN	ROADWAY	01	53	FAIR	AC	694	TERTIARY
	02/11/81	[FROM] E'LY EDGE MADISON			[TO] W'LY EDGE WILSON LN		
IMONR	ROADWAY	05	54	FAIR	PCC	1622	SECONDARY
	12/05/79	[FROM] S EDGE TAYLOR AVE			[TO] N EDGE BUNDY ST		
IWILN	ROADWAY	01	55	FAIR	AC	1670	TERTIARY
	11/29/79	[FROM] PERSHING AVE			[TO] JUST BEYOND JURASIN		
IBACK	ROADWAY	01	56	GOOD	AC	5155	TERTIARY
	02/04/80	[FROM] E EDGE HARRISON RD			[TO] W EDGE MULBRY IS RD		
ISKIF	ROADWAY	01	56	GOOD	PCC	1391	TERTIARY
	01/12/80	[FROM] BLDG 408			[TO] BLDG 414		
ITINC	ROADWAY	01	56	GOOD	AC	3068	TERTIARY
	01/09/80	[FROM] W ED MADI BLDG 2783			[TO] TINC02 BLDG 2798		
IMULB	ROADWAY	02	57	GOOD	AC	12551	PRIMARY
	02/20/80	[FROM] N EDGE WILSON AVE			[TO] ENTR PINES GOLF CLB		
IKELL	ROADWAY	01	58	GOOD	AC	3378	TERTIARY
	10/30/79	[FROM] S'LY EDGE MONROE			[TO] ROD & GUN CLUB		
IO4ST	ROADWAY	01	58	GOOD	AC	2020	TERTIARY
	11/09/79	[FROM] E'LE EDGE BULLARD			[TO] W'LY EDGE JACKSON		
IWRIG	ROADWAY	01	60	GOOD	PCC	1371	TERTIARY
	10/18/79	[FROM] E'LY EDGE WASH NO			[TO] W'LY EDGE WALKER ST		
IKERR	ROADWAY	01	63	GOOD	AC	4897	TERTIARY
	01/16/80	[FROM] N'LY EDGE LEE BLVD			[TO] BLDG 425 3RD FORT		
I12ST	ROADWAY	03	63	GOOD	AC	399	TERTIARY
	12/14/79	[FROM] E LY EDGE PATTON			[TO] W'LY EDGE LEE BLVD		
I13ST	ROADWAY	02	63	GOOD	AC	1038	TERTIARY
	12/14/79	[FROM] E LY EDGE JACKSON			[TO] W LY EDGE PATTON		
IGAFF	ROADWAY	01	64	GOOD	PCC	2152	TERTIARY
	10/22/79	[FROM] N EDGE MONROE AVE			[TO] S EDGE LEE BLVD		
IWASN	ROADWAY	03	64	GOOD	AC	4000	PRIMARY
	11/08/79	[FROM] S'LY SIDE HINES CIR			[TO] CENTER OF SOMERVELL		
I1EEB	ROADWAY	05	65	GOOD	AC	7688	PRIMARY
	11/15/79	[FROM] W'LY SIDE ANDERSON			[TO] HINES CIR		
IWASN	ROADWAY	05	65	GOOD	PCC	4453	SECONDARY
	11/09/79	[FROM] S'LY EDGE TAYLOR			[TO] N'LY EDGE WILSON		

Figure F2. (Continued)

APPENDIX G: CHECKLISTS AND EXPLANATORY
MATERIALS FOR MISCELLANEOUS FACILITIES

<u>Functional Use</u>	<u>Rating</u>
Training Facilities (Cat Codes 171 and 179)	8
Technical & Industrial Facilities (Cat Codes 210 thru 452)	7
Secondary Operating Facilities (Cat Codes 720 thru 730)	6
Utilities Plants & Alarm Systems (Cat Codes 810 thru 845 and 880 thru 890)	7
Administrative Facilities (Cat Codes 610 thru 690)	4
Morale & Recreational Facilities (Cat Codes 740 thru 760)	4
Transportation & Drainage Facilities (Cat Codes 851 thru 872)	7
Real Estate (Cat Codes 900 & above)	2

(2) Justification factors for the project.

Each project listed should be essential. Therefore, it will be assigned a basic rating:

	<u>Rating</u>	
Essential M&R	5	Basic

Additional points will be added where project accomplishment enhances one or more of the following factors:

H	Health	.3
S	Safety	3
E	Energy Conservation	See figure G-2
I	Environmental Conditions	2
T	Security of Government Property	2
W	Morale, Welfare, or Comfort	2

Figure G1. BMAR project validation and scoring procedures (TRADOC)

H-1. TRADOC Form 641-R, BMAR/DMAR Validation (fig G-1, app G), will be used to record results of the DMAR project review. One copy of the form will be prepared by the installation for each DMAR project presented for validation or revalidation. Part I will be completed, signed by an authorized official, and placed in the project folder prior to validation visit. The TRADOC validator will complete part II of the form. Two copies of the completed form will be reproduced for TRADOC use. The completed form will become a permanent part of the project documentation folder.

H-2. Scoring of DMAR Projects.

a. A numeric score for each M&R project estimated to cost \$1,000 or more will be assigned by the TRADOC validator. The assigned numeric score, in conjunction with design status, establishes a TRADOC priority system whereby projects will compete in the FHMA funding program. Factors to be considered in the score procedure are:

- (1) Category of family housing.
- (2) Category of requirement.
- (3) Type of work.
- (4) Condition of facility.
- (5) Priority assigned by the installation.

b. The above factors are further subdivided to facilitate assignment of the numeric rating.

- (1) Category of family housing (select only one).

<u>Alpha Character</u>	<u>Category</u>	<u>Rating</u>
A	Adequate housing	10
S	Substandard (including trailer sites)	8
O	Other real property	6

Figure G1. (Continued)

BMAH ALPHA/SCORE: SWA													23
SSC													
AS OF 30 SEP 80													
PUNE USE JUST FACTOR PROJ TYPE CONDITION BASE SEC. TO													
EST COST SCORE ALPHA/SCORE ALPHA/SCORE ALPHA/SCORE SCORE MD. 1103P10M													

*****</													

Figure G2. Sample worksheet (TRADOC)

MAINTENANCE AND REPAIR (OMA, OMAR AND APH)

Project Validation and Rating Procedures

A-1. The project validation will record results of the on-site project inspection.

A-2. The criteria governing classification of projects as maintenance and/or repair is contained in AR 420-10 and 210-50.

A-3. Rating of M&R projects including BMAR/DMAR projects.

a. Objectives. Assignment of a numeric rating to maintenance/repair projects is accomplished to indicate the degree of need for M&R. Factors to be considered are:

- (1) Facilities use Factor
- (2) Project Purpose Factor
- (3) Project Type Factor
- (4) Mission Factor
- (5) Condition Factor
- (6) Installation Priority

b. The first five factors listed above are further sub-divided into functional areas to facilitate assignment of a numeric rating. Installation priority is automatically entered into scoring process in item J of Project Rating Worksheet (FORSCOM Form 63-2). (Figure A-1 and Table A-1.)

(1) Facilities Use Factor - Reflects use of facility based on Construction Category Code (select only one type). Refer to AR 415-28

<u>Alpha Character</u>	<u>Type of Use</u>	<u>Rating Range</u>
A	Operational Facility (Cat Codes 110 thru 169)	5-10
B	Personnel Living Space (Cat Codes 710 -714 for APH and 720-725 for OMA & OMAR)	3-10
C	Training Facilities (Cat Codes 170 thru 179)	7-9
D	Hospital and Related Facilities (Cat Codes 310 thru 330)	7-9
E	Utilities Plants and Systems (Cat Codes 810 thru 845 and 850 thru 890)	5-9
F	Technical and Industrial Facility (Cat Codes 210 thru 452)	5-8
G	Morale and Recreational Facilities (Cat Codes 730 thru 760)	4-6
H	Transportation and Drainage Facilities (Cat Codes 850 thru 872)	4-6

Figure G3. FORSCOM priority rating system

<u>Alpha Character</u>	<u>Type of Use</u>	<u>Rating Range</u>
I	Administrative Facilities (Cat Codes 610 thru 690)	3-5
J	Others (Cat Codes 900 and above)	0-2

(2) Project Purpose Factor - Reflects primary purpose/area of interest of intended work.
(Select Basic rating plus one or more factors as applicable.)

<u>Alpha Character</u>	<u>Purpose of Maintenance and Repair</u>	<u>Rating Range</u>
A	Essential Facility Maintenance/Repair	5 Basic
B	Mission (Readiness, Training)	4-5
C	Health	2-4
D	Security	1-4
E	Safety	1-4
F	Energy Conservation	4-5
G	Environmental	1-4
H	Quality of Life, Moral, Welfare, Recreational	1-4
I	Command Interest	1-3
J	Cost Effectiveness	1-3
K	Traditional, historical or architectural significance	1-3
L	Other (Specify)	1-3

(3) Project Type Factor - Reflects IFS components description codes (select one only).

<u>IFS Code</u>	<u>Component Type</u>	<u>Rating</u>
01	Roofing	10
02	Structure	10
03	Floor Covering	2
04	Exterior Painting	4
05	Interior Painting	3
06	Heating	10
07	Air Conditioning	6
08	Plumbing	7
09	Electrical	8
10	Equipment	8
11	Utility Plant Equipment	9

Figure G3. (Continued)

FUNDING LEVEL DESCRIPTIONS					
WORK FUNCTION CATEGORY WITH FEATURE CODE	LEVEL 1	LEVEL 2	LEVEL 3	LEVEL 4	LEVEL 5
DREDG- ING- FLOOD CONTROL (33.1)	F05	NONE	Costs for dredging that would provide design dimensions flood flow beyond the budget year if cost savings of greater than \$51 would be achieved.	Costs for dredging that would provide design dimensions flood flow beyond the budget year if cost savings of greater than 251 would be achieved.	Costs for dredging that would provide dimensions flood flow beyond the budget year if cost savings of greater than 101 would be achieved.

Figure G4. Project operation and maintenance funding level matrix (Southwestern Division)

ITEM	P - Poor G - Good E - Excellent NC - No Change					Photo No.	Remarks
	P	G	E	See Note			
Plant Bowl _____							
Erosion _____							
Seepage _____							
Berms _____							
Pavement _____							
Vegetation _____							
Rodents _____							
Intake Structure _____							
Wingwalls _____							
Trash Racks _____							
Discharge Lines _____							
Pipe _____							
Erosion _____							
Outlet Structure _____							
Wingwalls _____							
Gates _____							
Pumping Plant _____							
Superstructure _____							
Substructure _____							
Motor Floor _____							
Pump Floor _____							
Valve Room _____							
Sleeve Coupling Chamber _____							
Galleries _____							
Water Seepage _____							
Pipe Leakage _____							
Instrumentation _____							
Monuments _____							
Piezometers _____							
Miscellaneous _____							
Water Tank _____							

Figure G5. Checklist for California aqueduct.